

A Technical Review of CNC Routing and Quality Assurance Protocols in Printed Circuit Board Manufacturing

Shelke Karan Machindra¹, Chhajed Rahul Vijaykumar², Dr. Ramesh Suryabhan Gadakh³

¹Student, Department of Mechanical Engineering, Sau. Sundarbai Manik Adsul Polytechnic, Chas, Ahilyanagar, India

²Guide, Department of Mechanical Engineering, Sau. Sundarbai Manik Adsul Polytechnic, Chas, Ahilyanagar, India

²Principal, Department of Mechanical Engineering, Sau. Sundarbai Manik Adsul Polytechnic, Chas, Ahilyanagar, India

ABSTRACT

Printed Circuit Boards (PCBs) constitute the core structural and inter-connective backbone of modern electronic systems. This review paper examines mechanical panel processing—specifically Computer Numerical Control (CNC) routing—within PCB fabrication workflows, drawing on industrial practices and defect data associated with Epitome Components Private Limited (Ahmednagar, Maharashtra). The study synthesizes operational methodologies across single-sided, double-sided, and High-Frequency/RF PCB fabrications. Critical processing parameters—including spindle velocity, feed rates, tool deflection, and datum registration—are analyzed alongside common mechanical failure modes such as routing shifts, slot dimension variances, and edge burring. Standardized quality control frameworks, Pokayoke (mistake-proofing) jigs, and preventive maintenance regimes are evaluated to establish actionable protocols for optimizing dimensional accuracy and yield.

Keywords: PCB manufacturing, CNC routing, quality control, defect analysis, panel processing, poka-yoke, Epitome Components.

I. INTRODUCTION

The global electronics manufacturing industry relies heavily on high-precision Printed Circuit Board (PCB) fabrication. While chemical etching, photolithography, and electroplating define electrical connectivity, mechanical processes determine the physical tolerances, panel separation, and structural profiles of the final product.

Among mechanical operations, CNC routing is critical for profile extraction, internal cutout formation, and breakaway tab creation. Because routing occurs late in the manufacturing sequence—often after high-value plating and surface finishing—routing errors risk scrapping fully populated or fully processed multi-board panels.

This paper reviews the CNC routing phase within PCB manufacturing workflows using technical literature and public manufacturing disclosures from Epitome Components Private Limited. Incorporated in 1994 in Ahmednagar, Maharashtra, Epitome Components produces single-sided, double-sided, and RF printed circuit boards. This study analyzes technical parameters, common defects, root-cause methodologies, and preventive quality systems applied in high-throughput PCB panel processing.

II. LITERATURE REVIEW & TECHNICAL BACKGROUND

A. Mechanics of PCB CNC Routing

CNC routing in PCB manufacturing is a high-speed peripheral milling process where solid carbide endmills or router bits remove material along a pre-programmed path (G-code/Gerber profile). Unlike metal milling, PCB routing involves heterogeneous composite materials—typically FR-4 (glass-reinforced epoxy), CEM-1, or high-frequency PTFE laminates—which induce distinct abrasive tool wear patterns.

Key operational variables governing profile accuracy include:

- Spindle Speed (N): Typically ranges from 20,000 to 60,000 RPM to maintain high surface cutting speed on small-diameter tools (0.8 mm to 2.4 mm).
- Feed Rate (f_r): The linear velocity of tool movement; incorrect feed-to-speed ratios cause excessive friction, chip clogging, or tool breakages.
- Depth of Cut (d_c): Often executed in single or multi-pass profiles depending on panel stack height.
- Chip Load (f_z): The thickness of material removed per cutting edge, influencing thermal dissipation and edge burr formation.

B. Structural Classification of Product Lines

1. Single-Sided PCBs: Substrates requiring simple outer profile routing and basic non-plated through-hole (NPTH) slots.
2. Double-Sided PCBs: Requiring precise top-to-bottom layer registration to ensure mechanical features align with inner circuit traces and pads.
3. RF / High-Frequency PCBs: Substrates (e.g., PTFE/Taconic/Rogers) requiring strict dimensional tolerance control to prevent dielectric disturbance along board edges.

III. Panel Fabrication and CNC Workflow Analysis

A typical PCB fabrication lifecycle follows a rigorous sequential workflow where mechanical panel processing acts as a bridge between surface finishing and final inspection.

[Raw Substrate Preparation] → [Imaging & Etching] → [Drilling & Plating]

[Final Inspection & QA] ← [CNC Routing / Profiling] ← [Solder Mask & Finish]

A. Panelization and Registration

To maximize throughput, individual circuit boards are arranged onto standardized master panels. Panelization relies on tooling holes and registration pins to maintain fixed spatial coordinates across multi-station processing. Misalignment during panel loading directly propagates as dimensional drift during the routing phase.

B. Machine Tooling and Setup Dynamics

Before executing routing operations, machine parameters must be validated:

- Program Revision Verification: Ensuring NC routing files match the updated Gerber drawing revisions to avoid path deviations.
- Tool Condition Assessment: Inspecting carbide routers for flute wear, micro-chipping, or resin buildup.
- Vacuum and Extraction Check: Maintaining high static pressure dust extraction to remove abrasive glass-epoxy debris during cutting.

IV. DEFECT CLASSIFICATION AND ROOT-CAUSE ANALYSIS

Industrial routing logs show that mechanical failures typically stem from tool breakdown, thermal degradation, or fixturing instability.

TABLE I: Comprehensive Matrix of Routing Defects, Root Causes, and Mitigations

Defect Mode	Physical Manifestation	Primary Root Cause	Corrective & Preventative Action
Routing Shift	Axis offset along board edge/profile	Panel movement during cutting; improper fixture pin alignment	Upgrade registration jigs; re-zero machine datums; mandate first-piece approval.
Missing NPTH Slot	Intended internal slot or cutout is unrouted	Tool breakage mid-cycle; missing block code in program	Implement broken-tool sensors; integrate optical detection pins on jigs.
Undersized Feature	Internal slots or cutouts below lower tolerance limit	Flute wear on router bit; incorrect cutter compensation offset	Institute strict tool-life limits; perform pre-operational tool diameter checks.
Oversized Feature	Cutout exceeds upper engineering tolerance limit	Tool spindle runout; incorrect tool installation diameter	Verify spindle runout tolerances; cross-check tool diameter via optical setters.
Edge Burring / Delamination	Fiber glass protrusion or copper lip tearing	Dull router bits; excessive feed rate causing thermal degradation	Optimize feed-to-speed ratios; replace worn tooling proactively.

A. Diagnostic Analysis: The Broken Tool Failure Mode

A critical failure mode identified in production environments is tool breakage during internal slot processing. If a small-diameter router breaks while cutting a non-plated through-hole (NPTH) slot, the machine may complete the outer contour without throwing a system alarm, yielding panels missing critical mechanical cutouts.

- Immediate Root Cause: Fatigue failure of the carbide router caused by resin loading or excessive chip pressure.
- Systemic Cause: Absence of real-time tool integrity monitoring or post-routing optical sensing.
- Corrective Engineering: Implementation of Poka-Yoke (Mistake-Proofing) jigs fitted with physical micro-switches or optical sensors that confirm slot penetration before panel unloading.

V. QUALITY CONTROL PROTOCOLS AND OPERATIONAL SAFETY

Quality assurance in PCB panel processing depends on shifting from reactive inspection to proactive process control.

Pre-Operational Setup Verification

- Gerber/NC file revision match
- Spindle runout and tool diameter optical check

First-Piece Inspection (FPI)

- 100% optical and CMM profile check
- Slot width and datum shift verification

In-Line Batch Monitoring

- Automated tool-life tracking
- Poka-yoke jig detection for slot completion

A. Quality Assurance Protocols

1. First-Piece Inspection (FPI): Validating the first routed panel from every batch on a Coordinate Measuring Machine (CMM) or optical measuring projector before releasing the lot.
2. Tool-Life Management (TLM): Establishing strict distance-based or hit-count limits (e.g., maximum linear meters routed per bit) rather than running tools to failure.
3. Traceability Controls: Enforcing strict revision tags linking physical routing fixtures directly to digital CAD/CAM files.

B. Environmental Health and Safety (EHS)

CNC routing generates fine FR-4 glass-epoxy dust, which poses respiratory risks and machine abrasion hazards. Recommended safety measures include:

- Closed-loop high-efficiency particulate air (HEPA) dust extraction.
- Interlocked machine enclosures to prevent contact with high-speed spindles.
- Mandatory personal protective equipment (PPE) during manual tool changes and fixture setups.

VI. DISCUSSION & INDUSTRIAL INSIGHTS

The technical findings highlight that mechanical routing—often viewed merely as an auxiliary cutting step—acts as a primary determinant of final PCB yield. Because panelization packs dozens of individual circuit images onto a single substrate, a single routing parameter drift (such as datum offset) invalidates the entire panel, destroying value accumulated across previous imaging, plating, and etching steps.

Implementing disciplined setup verification, automated tool monitoring, and physical Poka-Yoke detection methods significantly lowers scrap rates and reduces total manufacturing costs.

VII. CONCLUSION AND RECOMMENDATIONS

A. Key Findings

- CNC routing accuracy depends on the interlocked control of machine parameters, tooling condition, program versioning, and panel registration.
- Intermittent routing defects like missing slots or edge burring are preventable through automated tool-breakage detection and standardized preventive maintenance.
- Structured first-piece approval procedures prevent recurring systemic errors across high-volume panel runs.

B. Technical Recommendations

1. Integrate automatic tool-breakage detection sensors across all high-speed CNC routing heads.
2. Implement standardized setup checklists requiring dual sign-offs (Operator + QA Lead) before batch execution.
3. Apply mistake-proofing (Poka-Yoke) physical pin sensors to downstream inspection fixtures.
4. Transition from reactive tool replacement to predictive tool-life tracking based on cut distance.

REFERENCES

1. Epitome Components Private Limited, "Public corporate information and company profile," Ahmednagar, Maharashtra, 2026.
2. Ministry of Electronics and Information Technology (MeitY), "Reports on electronics components manufacturing sector in India," Government of India, Tech. Rep., 2024.
3. Epitome Components Pvt. Ltd., "Internal process quality analysis and root-cause defect reports," Technical Presentation Material, 2025.
4. M. Groover, *Fundamentals of Modern Manufacturing: Materials, Processes, and Systems*, 7th ed. Hoboken, NJ: Wiley, 2020.
5. IPC-A-600J, *Acceptability of Printed Boards*, IPC Standard Specification, 2020.

Appendix A: Operational Execution Checklist

TABLE II: Daily Operational and Quality Control Checklist

Inspection Domain	Specific Verification Point	Acceptance Criteria
Machine Spindle	Spindle runout, collet cleanliness, static pressure	Runout $< 5\,\mu\text{m}$; zero resin build-up on collet.
Tooling	Diameter, flute sharpness, carbide condition	Matches program specification; zero micro-chipping.
Software/NC File	File revision ID, depth offsets, feed rates	Matches master traveler document revision.
Fixture / Vacuum	Registration pin wear, vacuum pull strength	Zero axial play in pins; gauge within green operating zone.
First Output	Profile dimensions, slot presence, edge quality	100% compliant with optical comparator print specifications.