

Operational Analysis of CNC Routing in Printed Circuit Board (PCB) Manufacturing: An Industrial Case Study

Sagar Pranav Tukaram¹, Chhajed Rahul Vijaykumar², Dr. Ramesh Suryabhan Gadakh³

¹Student, Department of Mechanical Engineering, Sau. Sundarbai Manik Adsul Polytechnic, Chas, Ahilyanagar, India

²Guide, Department of Mechanical Engineering, Sau. Sundarbai Manik Adsul Polytechnic, Chas, Ahilyanagar, India

²Principal, Department of Mechanical Engineering, Sau. Sundarbai Manik Adsul Polytechnic, Chas, Ahilyanagar, India

ABSTRACT

Computer Numerical Control (CNC) machinery represents a cornerstone of modern industrial automation, ensuring high-precision, repeatable, and high-throughput fabrication. This paper presents an empirical analysis of CNC routing operations within Printed Circuit Board (PCB) manufacturing, grounded in operational data and practical training conducted at Epitome Components Private Limited in Ahmednagar, Maharashtra. The investigation systematically evaluates machine kinematics, workpiece clamping mechanics, multi-axis profile milling, cut-path verification, and operator protocol integration. Specific focus is directed toward optimizing the balance between spindle speed, tool wear, dimensional tolerance, and edge quality during depanelization and contour routing. Furthermore, the role of human-machine interaction, systematic quality inspection, and proactive safety management in minimizing scrapped panels and rework is detailed.

Keywords: CNC Routing, PCB Manufacturing, Computer-Controlled Machining, Depanelization, Process Optimization, Quality Assurance, Industrial Engineering.

INTRODUCTION

The global electronics manufacturing industry relies heavily on automation to meet rigid dimensional tolerances, tight production schedules, and high circuit density requirements. In Printed Circuit Board (PCB) fabrication, mechanical milling and depanelization are critical post-etching stages that define the final board geometries, internal cutouts, mounting slots, and edge finishes.

Computer Numerical Control (CNC) routing machines utilize multi-axis G-code instructions to execute complex vector profiles with sub-millimeter accuracy. Epitome Components Private Limited, located in Ahmednagar, Maharashtra, is a key PCB manufacturing plant in India specializing in single-sided, double-sided, and multi-layer board production. The plant utilizes high-speed CNC routing and automated V-scoring systems to execute precise panel separation and profile routing.

This paper synthesizes empirical observations and operational data gathered from the shop floor. It examines the machine architecture, sequential routing workflows, operator safety protocols, quality control checkpoints, and manufacturing advantages inherent to modern CNC routing in high-volume PCB manufacturing.

OBJECTIVES

The primary research objectives of this industrial case study are structured as follows:

1. **System Kinematics & Design:** To analyze the mechanical construction, control architecture, and functional subsystems of industrial CNC routing machines.

2. **Workflow Mapping:** To establish a standardized, multi-stage process sequence for PCB panel routing from receipt to final dispatch.
3. **Work-Holding & Loading Dynamics:** To evaluate the efficacy of pin-registration, mechanical clamping, and vacuum-bed fixating methods during high-speed cutting.
4. **HMI & Controller Operations:** To document the operational interaction between the operator, numerical control unit, and program execution.
5. **Tooling & Material Removal Mechanics:** To observe tool degradation, edge burr formation, copper clad cut quality, and auxiliary V-cut machinery operations.
6. **Quality Assurance Protocols:** To categorize post-machining defect modes (e.g., surface delamination, dimensional deviation, edge roughness) and establish inspection standards.
7. **Occupational Health & Safety:** To formalize personal protective equipment (PPE) and machine safety guidelines for high-speed rotational machinery.
8. **Yield Optimization:** To identify process improvements that minimize scrap rate, rework, and tool breakage.

MANUFACTURING FOCUS (PCB FABRICATION & DEPANELIZATION)

CNC Routing Machine Architecture

An industrial CNC PCB routing machine is a specialized computer-controlled 3-axis milling system optimized for processing rigid FR-4, polyimide, and aluminum-core substrates.

Component / Subsystem	Primary Function	Technical Specification / Description
Machine Bed	Base stability and structural rigidity	Polymer concrete or heavy granite structure to damp harmonic vibrations.
Work Holding System	Secure panel registration	Combined high-flow vacuum vacuum table and precision tooling pins (1 mm - 3.0 mm).
High-Speed Spindle	Rotational cutting force	Air-bearing or ceramic-bearing spindle delivering 20,000 - 60,000RPM.
Routing Tooling	Material removal	Solid carbide diamond-cut router bits (0.8mm - 2.4 mm diameter).
X/Y/Z Motion Drives	Axis motion execution	AC brushless servomotors coupled to high-precision ball screws or linear drives.
CNC Controller	Command execution	High-speed motion controller interpreting industrial G-code/M-code sequences.
Vacuum Extraction	Dust and chip evacuation	Integrated high-CFM extraction unit with HEPA filtration to eliminate conductive dust.

PCB CNC Routing Process Workflow

The routing sequence must follow a rigorous, 15-step standard operating procedure (SOP) to ensure dimensional repeatability and prevent substrate stress fractures:

1. **Material Receipt:** Transfer the batch panel set from preceding chemical/plating operations to the routing staging zone.
2. **Job Order Verification:** Verify panel ID, batch code, board thickness, layer configuration, and engineering drawings.
3. **Pre-Process Visual Inspection:** Inspect incoming panels for substrate warping, surface copper oxidation, or pre-existing mechanical damage.
4. **Machine Loading:** Align registration holes over precision locating pins on the sacrificial backup board.
5. **Fixture Securing:** Engagement of the vacuum extraction bed and mechanical edge clamps to eliminate panel flex during Z-axis plunge.
6. **Program Selection:** Load the validated, part-specific NC program from the local server or controller memory.
7. **Tooling Check:** Inspect router bit diameter, fluke condition, runout, and collet cleanliness.
8. **Parameter Setting:** Verify spindle speed (RPM), feed rate (mm/min), and Z-axis plunge depth.
9. **Cycle Initiation:** Execute the program cycle and engage automatic dust extraction systems.
10. **In-Process Monitoring:** Continuously observe audio-visual indicators, spindle load gauges, and chip extraction flow.
11. **Cycle Termination:** Automatic spindle retraction and power-down upon program completion.
12. **Panel Unloading:** Disengage vacuum, release clamps, and carefully extract routed sub-panels.
13. **Substrate & Station Cleaning:** De-dust panels using ionized air knives and vacuum clean the sacrificial board.
14. **Metrology & Inspection:** Measure key dimensions, board profile tolerances, slot widths, and inspect edge bevels.
15. **Downstream Handoff:** Package and transfer accepted PCB lots to final quality testing or assembly.

Role of the CNC Routing Machine Operator

The operator serves as the frontline control loop governing throughput, dimensional fidelity, and equipment availability. Key operational duties include:

- **Instruction Execution:** Cross-referencing shop-floor traveler tags with CAD-generated panel drawings.
- **Tool Management:** Monitoring cutter wear cycles, performing collet maintenance, and replacing worn bits before cut degradation occurs.
- **Controller Interface:** Operating the human-machine interface (HMI), executing feed-rate overrides when chatter is detected, and monitoring spindle load metrics.
- **Quality Assurance:** Executing immediate line-clearance checks using vernier calipers, micrometers, and pin gauges.
- **Housekeeping & Safety:** Enforcing zero-dust accumulation zones and adhering strictly to machine lockout/tagout procedures during tool changes.

Practical Work Performed During Training

During the industrial internship at Epitome Components Pvt. Ltd., direct hands-on training covered the following domain competencies:

- **Machine Setup & HMI Navigation:** Manual pulse generator (MPG) control, zero-point/work coordinate setting (G54-G59), and spindle calibration.
- **Routing Execution:** Executing outer perimeter cuts, complex non-rectangular board profiles, and internal mounting cutouts.

- **Copper Removal & V-Scoring:** Auxiliary operation of automatic V-cut machines for panel scoring, and manual clearance of excess copper pour along break-away tab channels.
- **Post-Machining Cleaning:** Operating de-burring stations and ultrasonic cleaning systems to flush particulate debris from unplated slots.
- **Quality Auditing:** Conducting optical microscope checks to evaluate copper burr height and glass-fiber protrusion along routed edges.

Safety Procedures

Personal Protective Equipment (PPE)

- Mandatory ANSI-approved safety glasses to protect against airborne fiber fragments.
- Hearing protection (NLR rated) to mitigate high-frequency spindle noise ($>85\text{ dB(A)}$).
- Anti-static, slip-resistant safety shoes.
- Strict prohibition of loose clothing, dangling jewelry, or long un-tied hair near high-rpm rotating spindles.

Machine Safety Mechanisms

- Pre-flight safety interlock checks: Verification that enclosure guards and light curtains are operational.
- Immediate E-stop triggering upon detection of abnormal machine acoustic vibration or spindle stalls.
- Interlocked vacuum systems preventing machine start unless suction pressure exceeds minimum operating thresholds.

Advantages of CNC Routing in PCB Manufacturing

1. High Precision & Repeatability: Achieves structural tolerances within $\pm 0.05\text{ mm}$ - $\pm 0.1\text{ mm}$ across thousands of identical panels.
2. Geometric Versatility: Easily mills complex non-linear contours, internal cutouts, multi-radius curves, and narrow slots that punching dies cannot replicate.
3. Low Mechanical Stress: Outperforms mechanical guillotine shearing or manual breaking by reducing internal layer flexure and micro-cracking of ceramic capacitors.
4. Programmatic Adaptability: Engineering design revisions require only rapid NC code modification without expensive hard-tooling re-tooling lead times.

LIMITATIONS

- Capital Expenditure: High initial acquisition cost for multi-spindle, high-RPM CNC machines and associated dust extraction infrastructure.
- Consumable Costs & Wear: High wear rate of micro-carbide router bits when cutting abrasive glass-reinforced FR-4 substrates requires frequent tool replacement.
- Substrate Dust Generation: Generates fine FR-4 fiberglass and copper particulate dust that necessitates continuous industrial extraction to avoid mechanical jamming and operator exposure.
- Process Speed Constraints: Sequential vector routing is inherently slower per panel than hard-die blanking or punching in ultra-high-volume commodity manufacturing.

RESULTS AND DISCUSSION

Operational observations gathered during the training period at Epitome Components demonstrate that process parameter tuning directly dictates panel yield and edge quality.

Optimal spindle speed (40,000 - 50,000 RPM) coupled with controlled feed rates (1.2 - 1.8 m/min) yielded the cleanest structural cuts with minimal edge burring. Deviations—such as excessive feed speeds—resulted in cutter deflection, dimensional drift, and premature tool snap. Conversely, excessively high spindle speeds relative to feed rate caused localized thermal friction, leading to resin smear and bit gumming.

Rigid panel fixation via vacuum backing was verified as a critical factor in avoiding board vibration, which is the primary root cause of edge delamination and trace fracturing near board perimeters.

FUTURE SCOPE

The evolution of PCB routing technology is moving toward fully automated, Industry 4.0-compliant manufacturing cells:

- **Machine Vision Integration:** Real-time camera alignment systems to compensate for panel warp and shrinkage dynamically during routing.
- **Predictive Tool Life Monitoring:** Sensor-driven acoustic vibration and load analysis to predict bit dulling and initiate tool changes prior to panel damage.
- **Laser-Mechanical Hybrid Routing:** Combining CO₂/UV laser cutting for thin flex-rigid sections with mechanical CNC routing for thick glass-epoxy sections.
- **Automated Robotic Load/Unload:** Integration of articulated robotic arms and AGVs/AMRs for hands-free panel handling and automatic box palletizing.

CONCLUSION

This study validates the vital role of CNC routing in contemporary PCB manufacturing, based on operational practices observed at Epitome Components Private Limited. High-speed spindle mechanics, combined with rigid work-holding, precise NC programming, and methodical quality checks, allow manufacturers to achieve the stringent tolerances demanded by modern microelectronics. By strictly adhering to operational workflows, monitoring tool wear, and enforcing shop-floor safety, production facilities can maintain high panel yield while minimizing scrap rates and rework costs.

REFERENCES

1. Epitome Components Private Limited, *Factory Technical Documentation and Standard Operating Procedures for PCB Fabrication*, Ahmednagar, Maharashtra, India.
2. López-Mera, G. H., Luna-Gómez, A. A., Cruz-Morales, R. D., & Tinoco-Varela, D., "Manufactura de tarjetas de circuito impreso utilizando tecnología de control numérico por entrada," *Pädi Boletín Científico de Ciencias Básicas e Ingenierías del ICBI*.
3. IPC-A-600 Series Standards, *Acceptability of Printed Boards*, IPC International Industry Association.
4. Coombs, C. F., *Printed Circuits Handbook*, 7th ed., McGraw-Hill Education.
5. Shop Floor Operational Logs & Machinery Observation Notes, CNC Routing Department, Epitome Components Pvt. Ltd.