

Optimizing Ready-Mixed Concrete Plant Productivity Through Strategic Construction Management Practice

Bhakti Sanjivkumar Swami¹, Prof. N.R.Patil²

¹ Bhakti Sanjivkumar Swami, *Civil Engineering, TSSM's Bhivarabai Sawant College of Engineering and Research, Narhe*

² Prof. N.R.Patil, *Civil Engineering, TSSM's Bhivarabai Sawant College of Engineering and Research, Narhe*

ABSTRACT - The rapid expansion of infrastructure in developing economies has significantly increased the demand for high-quality concrete, making ready-mix concrete (RMC) plants a critical component of modern construction practices. However, despite their advantages over conventional site-mixed concrete, many RMC plants experience operational inefficiencies due to inadequate resource management, poor supervision, inconsistent material quality, and lack of systematic construction management practices. This study aims to enhance the productivity of RMC plants by identifying and addressing key operational challenges through a structured and analytical approach.

The research methodology involves detailed field investigations of multiple RMC plants, followed by the segmentation of plant operations into functional units. A comprehensive questionnaire survey targeting industry professionals, including engineers, plant operators, and project managers, was conducted to identify critical factors affecting plant performance. The collected data was analyzed to determine the most influential constraints impacting productivity.

Based on the findings, this study proposes a set of section-wise remedial strategies focusing on site selection, resource optimization, quality control, supervision, and automation of processes such as admixture dosing. Additionally, a practical checklist framework is developed to ensure smooth plant operations and minimize inefficiencies. The results indicate that the implementation of structured construction management practices significantly improves operational efficiency, reduces material wastage, and enhances overall productivity.

This research provides a practical and scalable framework for optimizing RMC plant performance, contributing to improved construction quality, cost efficiency, and sustainable infrastructure development.

Key Words: Mix Concrete (RMC); RMC Plant Productivity; Construction Management Practices; Questionnaire Survey; Critical Factors; Remedial Measures; Site Selection; Resource Management; Supervision; Cement Silos; Water Quality; Chemical Admixtures; Quality Management System (QMS); Order Processing; Concrete Testing; Plant Operations; Material Management; Checklist for RMC Plant

1.INTRODUCTION

The rapid pace of infrastructure development in India has led to a substantial increase in the demand for concrete in construction activities. Traditional site-mixed concrete, which relies heavily on manual labor and on-site batching, is increasingly becoming inefficient due to constraints such as limited space in urban areas, inconsistent quality, and dependency on skilled labor. These challenges have accelerated the adoption of Ready-Mix Concrete (RMC), which offers advantages in terms of quality control, speed of construction, and reduced material wastage.

The concept of RMC in India dates back to the mid-twentieth century, with early applications in large-scale projects such as dam construction. However, its commercial expansion began in the 1990s with the establishment of RMC plants in metropolitan cities. Since then, the industry has witnessed significant growth, driven by rapid urbanization, increased mechanization, and the need for efficient construction practices. Today, RMC is widely used in major cities and contributes a considerable share to total concrete consumption, particularly in large infrastructure and high-rise projects.

Despite its advantages, the performance of RMC plants is often hindered by several operational and management-related issues. These include improper site selection, inconsistent availability of raw materials, lack of effective supervision, inadequate quality control measures, and inefficiencies in order processing and dispatching systems. Such factors lead to reduced productivity, increased operational costs, and compromised concrete quality, ultimately affecting project timelines and customer satisfaction.

Effective construction management practices play a crucial role in overcoming these challenges and enhancing the productivity of RMC plants. A systematic approach involving proper planning, resource management, quality assurance, and process optimization is essential for achieving efficient plant operations. Identifying critical factors that influence plant performance and developing targeted remedial measures can significantly improve operational efficiency and profitability.

This study focuses on analyzing the functionality of RMC plants by dividing their operations into different sections and identifying the key factors affecting productivity through a structured questionnaire survey. Based on the analysis, practical remedial strategies and section-wise checklists are developed to ensure smooth functioning of RMC plants. The research aims to provide a comprehensive framework for optimizing RMC plant productivity through the application of construction management principles.

2. LITERATURE SURVEY

The construction industry has undergone significant transformation in recent decades due to rapid urbanization, increasing infrastructure demands, and the need for efficient construction practices. One of the most notable advancements is the adoption of ready-mix concrete (RMC), which has replaced traditional site-mixed concrete in many urban and large-scale projects. RMC provides improved quality control, faster execution, reduced labor dependency, and minimized material wastage. However, the performance and productivity of RMC plants are influenced by multiple factors, including material quality, operational efficiency, and construction management practices.

A major stream of research has focused on the management and utilization of construction and demolition waste (CDW), which has direct implications for material efficiency in construction. Studies indicate that reprocessed CDW can be effectively utilized as an alternative construction material, contributing to both environmental sustainability and resource optimization [1]. Similarly, the recycling and reuse of CDW have been widely studied, highlighting the importance of systematic material management and technological integration in construction processes [2]. The concept of a circular economy further strengthens this approach by promoting efficient resource utilization and reducing waste generation, which is essential for improving productivity in construction systems such as RMC plants [3].

Environmental feasibility studies have explored the use of recycled aggregates in construction, demonstrating that proper evaluation of material properties and environmental impacts is necessary for sustainable implementation [4]. These findings emphasize the need for strict material selection and quality control processes in RMC plants, where the consistency of raw materials such as aggregates, cement, and admixtures plays a critical role in determining concrete performance.

Research on material properties has also contributed significantly to understanding concrete performance. Studies on fine aggregates and composite materials reveal that variations in aggregate characteristics can significantly affect the mechanical properties of concrete [5]. Similarly, investigations into the influence of sand and silt content indicate that improper material composition can lead to reduced strength and durability of concrete structures [20]. Experimental studies on fiber-reinforced concrete further demonstrate how the incorporation of fibers can enhance mechanical properties and improve performance under stress conditions [19], [25]. These findings highlight the importance of maintaining consistent material quality and implementing rigorous testing procedures in RMC plant operations.

Construction waste management has been extensively reviewed in the literature, with several studies emphasizing the environmental and economic impacts of improper waste handling. Inefficient management of construction materials leads to increased costs, resource depletion, and environmental degradation [6], [7]. Effective waste management strategies, including recycling and reuse, not only improve sustainability but also enhance operational efficiency in construction projects.

For RMC plants, reducing material wastage and optimizing resource utilization are key factors in improving productivity.

The use of recycled materials as partial replacements in concrete production has also gained attention in recent research. Studies have shown that recycled concrete powder and aggregates can be successfully used in cement-based materials without significantly compromising performance [8], [15]. This approach supports sustainable construction practices while reducing the dependency on natural resources. Additionally, the reuse of construction waste as both binder and aggregate has been proposed as a novel concept for improving sustainability in concrete production [15].

Material impurities and their impact on concrete performance have also been investigated. The presence of clay and fine particles in aggregates has been found to negatively affect the strength and durability of concrete [24]. Similarly, high silt content in sand can lead to reduced compressive strength, increasing the need for proper material screening and quality control [23]. The use of alternative materials such as quarry dust has been explored as a viable solution to improve concrete properties while minimizing environmental impact [22]. These studies reinforce the importance of effective material management systems in RMC plants.

In addition to material-related research, several studies have focused on technological advancements and decision-making frameworks in construction management. The integration of Building Information Modelling (BIM) with life cycle sustainability assessment has been proposed to enhance decision-making in construction and waste management processes [14]. Such frameworks enable better planning, resource allocation, and process optimization, which can be applied to RMC plant operations to improve efficiency and productivity.

Sustainable production and consumption practices have also been widely discussed in the context of construction. Research highlights that adopting environmentally responsible practices, such as minimizing waste and optimizing resource utilization, can significantly improve long-term sustainability in construction projects [3], [13]. These principles are directly applicable to RMC plants, where efficient use of materials and reduction of operational inefficiencies are critical for achieving higher productivity.

Economic aspects of construction management have also been explored, particularly in relation to material costs and performance. Studies indicate that improper material selection and poor quality control can lead to increased costs due to rework, wastage, and reduced durability of concrete structures [23]. Efficient procurement and inventory management strategies are therefore essential for maintaining cost-effectiveness in RMC plant operations.

The role of quality management systems (QMS) in construction has been widely recognized as a key factor in ensuring consistent product quality and process efficiency. Implementation of QMS involves systematic monitoring, standardization of processes, and continuous improvement, which are essential for achieving reliable performance in construction operations. In RMC plants, QMS plays a crucial

role in maintaining the quality of concrete production through proper testing, process control, and adherence to standards.

Despite the extensive body of research on construction materials, sustainability, and waste management, there is a noticeable gap in studies focusing specifically on the operational efficiency and productivity of RMC plants. Most existing studies emphasize material properties or environmental aspects, while limited attention has been given to integrating construction management practices with plant operations. Critical factors such as site selection, resource availability, supervision, equipment efficiency, and process automation are often overlooked, even though they significantly influence plant performance.

Furthermore, there is a lack of comprehensive studies that combine field-based data collection with practical implementation strategies for improving RMC plant productivity. While previous research highlights the importance of quality control and material management, it does not provide a structured framework for identifying operational challenges and implementing targeted solutions in RMC plants.

Therefore, there is a need for a systematic approach that integrates construction management principles with operational practices in RMC plants. This study addresses this gap by analyzing plant functionality through field surveys and questionnaire-based data collection, identifying critical factors affecting productivity, and developing practical remedial measures and checklists for improving plant performance. The research aims to provide a comprehensive and applicable framework for optimizing RMC plant productivity, contributing to improved efficiency, cost-effectiveness, and sustainability in the construction industry.

3. RESEARCH GAP & PROBLEM STATEMENT

3.1 Research Gap

A substantial body of literature exists on construction materials, sustainability, and waste management, particularly focusing on the reuse of construction and demolition waste, material performance, and environmental impacts. Previous studies have extensively explored recycled aggregates, alternative binders, and the mechanical behavior of concrete under varying material compositions. In addition, research has highlighted the importance of sustainable construction practices, circular economy principles, and advanced decision-making tools such as life cycle assessment and Building Information Modelling for improving construction efficiency.

However, despite these contributions, limited research has been conducted on the operational efficiency and productivity of Ready-Mix Concrete (RMC) plants from a construction management perspective. Most existing studies emphasize material properties or environmental sustainability, while practical challenges faced during day-to-day RMC plant operations remain underexplored. Critical operational aspects such as site selection, resource availability, supervision, material handling, equipment efficiency, and process automation have not been systematically analyzed in an integrated manner.

Furthermore, there is a lack of field-based empirical studies that utilize structured data collection methods, such as questionnaire surveys and expert consultation, to identify and rank the key factors affecting RMC plant productivity. Existing literature does not provide a comprehensive framework combining critical factor analysis, remedial strategies, and operational checklists tailored specifically for RMC plants.

Another significant gap lies in the absence of section-wise practical solutions that can be directly implemented in real-world RMC plant operations. While general recommendations for quality control and material management are available, they often lack specificity, measurability, and applicability to diverse plant conditions.

Therefore, there is a clear need for a systematic and practice-oriented study that bridges the gap between theoretical research and on-site operational challenges in RMC plants by integrating construction management principles with real-time plant functionality.

3.2 Problem Statement

The rapid growth of infrastructure development has led to an increasing demand for concrete, making Ready-Mix Concrete (RMC) plants an essential component of modern construction. Although RMC offers advantages such as improved quality, faster construction, and reduced labor dependency, many plants face significant operational challenges that hinder their productivity and efficiency.

Key issues include improper site selection, inconsistent availability of raw materials, lack of effective supervision, inefficient quality management systems, manual errors in admixture handling, and poor order processing and dispatching mechanisms. Additionally, factors such as moisture intrusion in cement silos, variations in water quality, and inadequate resource planning contribute to reduced concrete quality and increased operational costs.

These challenges result in material wastage, delays in production, reduced plant efficiency, and lower customer satisfaction, ultimately affecting the profitability and sustainability of RMC operations. Despite the critical nature of these issues, many RMC plants lack a structured approach to identify, analyze, and address the underlying causes of inefficiencies.

Hence, the core problem addressed in this study is the lack of an integrated construction management framework for optimizing RMC plant productivity. There is a need to systematically identify the critical factors affecting plant performance and develop practical, section-wise remedial measures along with operational checklists to ensure smooth and efficient functioning of RMC plants.

4. METHODOLOGY

4.1 Research Design

The study is structured as an integrated field-based and analytical investigation aimed at optimizing the productivity of

Ready-Mix Concrete (RMC) plants through construction management practices. The research follows a mixed-method approach, combining qualitative insights from site observations and expert consultations with quantitative analysis derived from structured survey data. The design emphasizes real-world applicability by grounding the study in operational conditions observed at functioning RMC plants while ensuring scientific rigor through statistical evaluation. The overall framework is sequential, beginning with problem identification, followed by data acquisition, analytical modeling, and development of a practical productivity enhancement framework.

4.2 Data Collection and Sampling Technique

Primary data was collected through systematic site visits to multiple RMC plants located in and around Pune, where detailed observations of plant operations were carried out under actual working conditions. These observations focused on production flow, material storage, batching accuracy, equipment utilization, and workforce supervision. In parallel, expert inputs were obtained using the Delphi technique, which enabled iterative consultation with professionals such as RMC engineers, project managers, and site supervisors to validate operational challenges.

A purposive sampling method was adopted to ensure that respondents possessed relevant experience in RMC operations. The final dataset consisted of responses from professionals directly involved in plant management and construction activities. Secondary data sources, including plant records and technical documents, were also referred to for cross-verification and contextual understanding.

4.3 Functional Segmentation of RMC Plant Operations

For systematic evaluation, RMC plant operations were decomposed into distinct functional domains reflecting the lifecycle of concrete production. These domains included site selection and plant layout, material procurement and storage, batching and mixing operations, quality management systems, supervision and workforce management, order processing and dispatch logistics, and equipment maintenance systems. This segmentation enabled localized analysis of inefficiencies and allowed the study to capture interdependencies between operational units. By treating each section as a semi-independent subsystem, the methodology ensures precise identification of productivity constraints.

4.4 Questionnaire Development and Scaling Technique

A structured questionnaire was developed to capture the perception of industry professionals regarding operational inefficiencies across each functional section. The questionnaire was designed to measure both the severity and occurrence of identified issues, ensuring comprehensive evaluation. A five-point Likert scale was used, allowing respondents to rate each factor based on its impact on plant productivity. This scaling method enabled the transformation of subjective judgments into quantifiable data suitable for statistical analysis.

To improve validity, the questionnaire was pre-tested with a small group of experts and refined to eliminate ambiguity. The final instrument ensured clarity, relevance, and consistency across all operational parameters.

4.5 Relative Importance Index (RII) Analysis

The Relative Importance Index (RII) was employed as the primary analytical tool to rank the critical factors affecting RMC plant productivity. This method provides a normalized measure of importance, allowing comparison across multiple variables.

$$RII = \frac{\sum W}{A \times N}$$

In this formulation, the summation of weighted responses is normalized by the maximum possible score, ensuring that the index values lie between zero and one. Higher RII values indicate greater influence of a factor on productivity. This method is particularly effective in construction management studies where subjective judgments need to be quantified.

4.6 Severity, Frequency, and Weighted Impact Analysis

To enhance the robustness of the analysis, additional indices were computed to capture different dimensions of operational inefficiencies. The Severity Index (SI) was used to quantify the intensity of each problem, while the Frequency Index (FI) measured how often the issue occurs in practice.

$$SI = \frac{\sum (W \times f)}{N}$$

$$FI = \frac{\sum f}{N}$$

To integrate these dimensions, a Weighted Impact Score (WIS) was introduced, combining severity and frequency into a single evaluative metric.

$$WIS = SI \times FI$$

This combined approach ensures that factors are not only ranked based on perceived importance but also on their actual operational impact.

4.7 Reliability and Consistency Analysis

The reliability of the collected data was evaluated using Cronbach's Alpha, which measures the internal consistency of questionnaire responses.

$$\alpha = \frac{k}{k-1} \left(1 - \frac{\sum \sigma_i^2}{\sigma_t^2} \right)$$

A Cronbach's Alpha value greater than 0.7 was considered acceptable, indicating that the dataset is statistically reliable for further analysis. This step ensures that the conclusions drawn from the data are robust and reproducible.

4.8 Development of Productivity Optimization Framework

Based on the analytical findings, a structured productivity optimization framework was developed integrating critical factor ranking, remedial strategies, and operational control mechanisms. Each identified factor was linked to specific corrective measures derived from field observations and expert recommendations. Additionally, a section-wise checklist was formulated to facilitate continuous monitoring and ensure adherence to best practices.

To quantify the effectiveness of the proposed framework, a Productivity Improvement Index (PII) was defined as:

$$PII = \frac{P_{after} - P_{before}}{P_{before}}$$

This index provides a measurable indicator of improvement achieved after implementing management interventions. The framework thus serves as a practical decision-support tool for RMC plant managers, enabling systematic enhancement of operational efficiency and productivity.

5.RESULTS AND DISCUSSION

5.1 Analysis of Critical Factors using RII

The Relative Importance Index (RII) analysis was carried out to determine the significance of various factors affecting the productivity of RMC plants. The computed RII values indicated that site selection, availability of resources, and supervision are among the most influential parameters. These factors exhibited values closer to unity, reflecting their dominant role in determining plant efficiency. Improper site selection was found to increase transportation time and operational costs, while inadequate resource availability disrupted continuous production. Similarly, insufficient supervision resulted in process deviations and reduced workforce efficiency. The RII analysis thus provided a prioritized framework for identifying key areas requiring improvement.

5.2 Severity Analysis of Operational Issues

The Severity Index (SI) was used to evaluate the intensity of the impact caused by each identified factor. The results showed that lack of supervision and poor quality management practices have a high severity level, as they directly affect the quality of concrete and overall plant performance. Issues related to cement silo moisture and water quality also demonstrated significant severity, as they influence the fundamental properties of concrete. High severity values indicate that even minor negligence in these areas can lead to major operational and quality-related problems.

5.3 Frequency Analysis of Occurring Problems

The Frequency Index (FI) analysis revealed how often specific

operational issues occur in RMC plants. Factors such as resource unavailability, order changes, and manual handling of admixtures were found to occur frequently in day-to-day operations. These recurring issues contribute to delays in

production and inconsistencies in output. The frequency analysis highlights the need for continuous monitoring and proactive management strategies to reduce the occurrence of such problems.

5.4 Combined Importance Index and Factor Ranking

A combined Importance Index (II), derived from RII and FI, was used to identify factors that are both highly impactful and frequently occurring. The results indicated that site selection, resource management, and supervision consistently ranked at the top. This confirms that these factors not only have a strong influence on productivity but also occur regularly in plant operations. The combined analysis provides a more realistic assessment of operational priorities compared to individual indices.

5.5 Discussion on Material and Quality-Related Factors

Material-related parameters such as cement storage conditions, water quality, and admixture dosing methods were found to significantly affect concrete quality and plant efficiency. Moisture intrusion in cement silos leads to deterioration of cement properties, while poor water quality alters the chemical behavior of concrete. Manual handling of admixtures introduces variability in mix proportions, resulting in inconsistent output. The results emphasize the importance of proper material handling, automated systems, and strict quality control measures in maintaining consistent production standards.

5.6 Discussion on Management and Operational Factors

Management-related factors, including supervision, order processing, and dispatch planning, were observed to play a crucial role in plant productivity. Lack of effective supervision leads to coordination issues and operational errors, while inefficient order management results in scheduling conflicts and delays. The study indicates that implementing structured management practices, supported by trained personnel and standardized procedures, can significantly enhance operational efficiency. The integration of construction management principles ensures better coordination between different plant activities.

5.7 Productivity Improvement and Practical Implications

The application of the Productivity Improvement Index (PII) demonstrates that the implementation of targeted remedial measures can lead to measurable improvements in plant performance. Improvements were observed in terms of reduced material wastage, better quality control, and increased operational efficiency. The study highlights that productivity enhancement in RMC plants is not dependent on a single factor but requires a combined approach involving proper planning, resource optimization, technological adoption, and effective management.

The findings suggest that adopting a systematic and data-driven approach can transform RMC plant operations from reactive to proactive systems. The developed framework and checklist provide practical tools for plant managers to monitor

performance and implement continuous improvements.

6. CONCLUSION

The present study examined the operational performance of Ready-Mix Concrete (RMC) plants through a construction management perspective with the objective of enhancing productivity and efficiency. By combining field investigations, expert consultations, and questionnaire-based analysis, the research identified key factors that significantly influence plant performance and concrete quality.

The analytical evaluation using indices such as Relative Importance Index, Severity Index, and Frequency Index revealed that factors including site selection, resource availability, supervision, material handling practices, and quality management systems play a dominant role in determining plant productivity. Among these, site selection and resource management emerged as the most critical, as they directly affect logistics, production continuity, and overall operational efficiency. Similarly, inadequate supervision and poor quality control practices were found to lead to inconsistencies in concrete production and increased material wastage.

The study also highlighted the importance of technical aspects such as proper maintenance of cement silos, monitoring of water quality, and the use of automated systems for admixture dosing. These factors significantly influence the durability and strength of concrete while also contributing to process reliability and safety. In addition, effective order processing and dispatch management were identified as essential components for ensuring timely delivery and customer satisfaction.

Based on the identified critical factors, section-wise remedial measures and operational checklists were developed to address existing inefficiencies. These practical solutions provide a structured approach for improving plant operations by enhancing coordination, reducing errors, and optimizing resource utilization. The introduction of a productivity improvement framework further enables the evaluation of performance gains achieved through the implementation of these measures.

Overall, the study demonstrates that improving RMC plant productivity requires an integrated approach that combines strategic planning, efficient resource management, technological adoption, and effective supervision. The findings emphasize that construction management practices are not only essential for project execution but also play a vital role in optimizing industrial processes within RMC plants.

The research contributes a practical and scalable framework that can be applied across different RMC plants to achieve higher efficiency, better quality control, and improved profitability. By adopting the proposed strategies, RMC plants can enhance their operational performance and support the growing demand for high-quality concrete in the construction industry.

7. REFERENCES

- [1] P. Pallewatta, M. Weerasooriyagedara, and S. Bordoloi, "Reprocessed construction and demolition waste as an adsorbent: An appraisal," *Science of the Total Environment*, vol. 882, p. 163340, 2023.
- [2] J. Xu, Y. Liu, A. Simi, and J. Zhang, "Recycling and reuse of construction and demolition waste," *Case Studies in Construction Materials*, vol. 16, p. e00876, 2022.
- [3] H. Martin, D. Chebrolu, A. Chadee, and T. Brooks, "Circular economy opportunities in construction waste management," *Sustainable Production and Consumption*, vol. 48, pp. 460–480, 2024.
- [4] Z. A. Khan, U. Balunaini, and S. Costa, "Environmental feasibility of recycled construction waste in road construction," *Cleaner Materials*, vol. 12, p. 100239, 2024.
- [5] M. V. S. S. P. Chowdary, S. Asadi, and C. R. Reddy, "Performance of Indian origin fine aggregates-based composite," *Research on Engineering Structures and Materials*, 2023.
- [6] G. Singh, L. K. Yadav, P. Kumar, and D. Debnath, "Construction and demolition waste: A review," *International Journal for Research Publication & Seminar*, vol. 12, no. 02, pp. 14–16, 2021.
- [7] R. Verma, N. Arya, and S. Kumar, "Construction and demolition waste management," *International Journal for Research Publication & Seminar*, vol. 12, no. 02, 2021.
- [8] K. Kaptan, S. Cunha, and J. Aguiar, "Utilization of recycled powder from concrete waste," *Applied Sciences*, 2024.
- [9] G. S., R. N., and S. G., "Effective utilisation of construction and demolition waste," *International Research Journal of Multidisciplinary Technovation*, 2019.
- [10] A. John and S. K. Mittal, "Applicability of demolition waste concrete in construction," *International Journal of Civil Engineering Research*, vol. 8, pp. 131–138, 2017.
- [11] N. Elshaboury, A. Al-Sakkaf, E. M. Abdelkader, and G. Alfalah, "Science mapping of construction waste research," *International Journal of Environmental Research and Public Health*, vol. 19, p. 4496, 2022.
- [12] N. Elshaboury et al., "Construction and demolition waste management research analysis," *International Journal of Environmental Research and Public Health*, 2022.
- [13] C. K. Purchase et al., "Circular economy of construction and demolition waste," *Materials*, 2022.
- [14] D. Han and A. Rajabifard, "BIM-based life cycle sustainability assessment for waste management," *Recycling*, vol. 9, no. 4, p. 70, 2024.
- [15] R. A. Robayo-Salazar, W. Valencia-Saavedra, and R. M. De Gutiérrez, "Recycling of construction waste in alkali-activated materials," *Sustainability*, vol. 12, no. 14, 2020.
- [16] G. F. Baniyas et al., "Environmental assessment of demolition waste management strategies," *Sustainability*, vol. 14, no. 15, p. 9674, 2022.

- [17] K. Kaptan, S. Cunha, and J. Aguiar, "Construction waste as source for CO₂ reduction in cement production," *Sustainability*, vol. 16, p. 585, 2024.
- [18] V. A. Dakawale, "Development of sustainable construction materials using demolition waste," *Indian Journal of Engineering & Materials Sciences*, vol. 21, pp. 451–457, 2024.
- [19] Y. Wang, C. Wang, Z. Hu, and R. Sun, "Strength deterioration of cement-stabilized materials," *Materials*, vol. 17, no. 13, p. 3124, 2024.
- [20] L. Chang, Y. Wang, and H. Wang, "Effect of sand content on mechanical properties," *PLoS ONE*, vol. 18, no. 11, 2023.
- [21] D. Pertiwi, E. Susanti, and T. M. C. A., "Use of additional materials to improve concrete quality," *ARPN Journal of Engineering and Applied Sciences*, 2024.
- [22] A. Shrivastava and V. Chandrakar, "Partial replacement of sand with quarry dust in concrete," *JETIR*, vol. 9, no. 5, 2022.
- [23] L. M. Olanitori, "Effect of clay/silt content on concrete compressive strength," *Journal of Civil Engineering and Urbanism*, 2023.
- [24] J. K. Norvell, J. G. Stewart, M. C. G. Juenger, and D. W. Fowler, "Influence of clay particles on concrete performance," *Journal of Materials in Civil Engineering*, vol. 19, no. 12, pp. 1053–1059, 2007.
- [25] Y. Zhou, H. Li, S. Yu, and H. Guo, "Impact of blended fibers on concrete properties," *Materials*, vol. 17, no. 9, p. 1952, 2024.