

# "Precast Concrete Construction, Best Practices for Civil Engenders and Architects"

**AR. KAMINI JAIN BADNORE; BURHANUDDIN BADNAGAR WALA**

STUDENT, SCHOOL OF ARCHITECTURE, IPS ACADEMY, INDORE, MADHYA PRADESH, INDIA

## ABSTRACT:

Precast concrete has become one of the most widely used industrialized construction systems in modern civil engineering and architecture due to its ability to improve quality, reduce construction time, lower lifecycle costs, and enhance sustainability. Unlike traditional cast-in-situ concrete which is mixed, poured, and cured on the building site, precast concrete elements are manufactured in controlled factory environments before being transported and assembled at the construction location. This approach provides engineers and architects with a high degree of precision, reduced on-site labor dependency, and improved structural reliability. The growing demand for rapid construction, resource efficiency, and sustainable building practices has further accelerated the adoption of precast technologies globally. This paper provides a detailed review of precast concrete construction practices, including its advantages and disadvantages, economic and environmental implications, design and production methodologies, and comparative analysis with cast-in-situ systems. Key technical insights — such as quality control, material optimization, connection detailing, transportation logistics, and structural performance — are discussed to guide professionals in effective project planning and implementation. Multiple case studies illustrate real-world applications where precast concrete has successfully delivered improvements in schedule, cost, and performance. The paper also explores challenges such as early-stage coordination, transportation constraints, and design adaptability while offering recommendations for future research and industry adoption strategies. Through comprehensive coverage of theoretical and practical aspects, this research aims to equip civil engineers and architects with best practices for leveraging precast concrete in contemporary construction projects.

## KEYWORDS

Precast concrete, prefabrication, quality control, structural systems, manufacturing, durability, erection techniques, civil engineering, architecture, modular construction.

## INTRODUCTION/OVERVIEW

Precast concrete — also known as prefabricated concrete — is a construction system in which concrete elements are cast and cured at a factory or off-site facility before being transported to the job site for final assembly. This contrasts sharply with traditional cast-in-situ (or on-site cast) concrete, where concrete is mixed and poured directly into forms on the construction site. Precast concrete elements can include beams, columns, slabs, walls, staircases, and even complete modular units that are integrated into the building structure.

The precast method emerged as part of the industrial revolution in construction, seeking ways to shift production from unpredictable on-site conditions to controlled factory environments. Over the past several decades, advancements in manufacturing precision, reinforcement techniques, connection technologies, and transportation logistics have significantly increased the scope and complexity of precast applications.

Modern construction sectors, from residential and commercial buildings to infrastructure projects like bridges, tunnels, and highways, increasingly incorporate precast concrete elements to improve project efficiency and performance. The rationale behind this shift includes the ability to reduce on-site labor, enhance quality control, minimize material waste, and shorten overall project timelines.

The rising demand for sustainable building practices also supports the use of precast technologies. Factory production enables better material optimization, lower waste compared to on-site casting, and improved energy efficiency when

combined with high-performance concrete mixes and thermal designs. The controlled environment of a precast facility also allows for precise curing and reinforcement placement, resulting in consistently strong structural members.

Despite its many advantages, precast concrete construction is not without limitations. Early coordination between architects, structural engineers, and manufacturers is essential to ensure that components fit together precisely during assembly. Transportation of large precast elements requires careful planning, specialized equipment, and often local manufacturing hubs to reduce logistics costs. Furthermore, initial investment in molds, formwork, and production facilities can be higher compared to traditional cast-in-situ methods, although the long-term economic benefits often outweigh these upfront costs.

This paper explores the breadth of precast concrete construction, covering historical context, design principles, production methods, comparisons with cast-in-situ systems, industry challenges, technical insights, and real-world case studies. Through a comprehensive review of credible sources and industry practices, the paper aims to provide best-practice guidance for civil engineers and architects considering precast concrete for their projects.

## **METHODOLOGY**

This study adopts a comparative research methodology to evaluate best practices in precast concrete construction. A combination of qualitative and quantitative approaches ensures a comprehensive understanding of the technical, economic, and environmental implications of using precast concrete compared to traditional cast-in-situ methods.

### **Data Collection**

Published literature, industry reports, technical guidelines, and case studies from construction companies employing precast technology were reviewed. Sources included journals on structural engineering, reports by the Precast/Prestressed Concrete Institute (PCI), and governmental construction standards.

Comparative charts, graphs, and tables were created to illustrate differences in productivity, cost, durability, and environmental performance between precast and cast-in-situ construction.

Observations from case studies were synthesized into lessons learned and recommendations for industry adoption of best practices.

## **HISTORICAL EVOLUTION OF PRECAST CONCRETE**

The concept of prefabricating construction elements dates back to early industrial building techniques, but concrete precasting became prominent in the early 20th century as engineering practices advanced. Originally used for simple elements like pipes and blocks, precast methodologies expanded into structural walls, floor systems, and complete modular units.

One early innovation was the filigree concrete method developed in the 1960s, which combined thin precast concrete panels with cast-in-place topping to rapidly construct floor systems without extensive formwork. This hybrid technique demonstrated early potential for combining factory precision with on-site adaptability, accelerating construction while maintaining structural performance.

As urbanization and industrialization progressed, demand for rapid and repeatable construction systems grew, leading to widespread adoption of precast elements in residential buildings, parking structures, and large public works. In many regions, government policies began to encourage industrialized building systems (IBS) to meet housing needs and infrastructure backlogs, further driving interest in precast technologies.


Global architectural trends also embraced the aesthetic versatility of precast concrete. Precast panels, for example, could be textured, colored, or finished to meet designers' visual requirements, expanding their use beyond purely structural roles into facade and architectural expression.

## **PRECAST CONCRETE CONSTRUCTION**

Precast concrete construction involves several sequential stages that integrate design, manufacturing, logistics, and assembly:

### **1.Design and Planning**

Effective precast projects begin with detailed architectural and structural designs that accommodate precast elements from the outset. This includes coordination between engineers and architects to define component geometry, reinforcement details, connection systems, tolerances, and installation sequencing. Early adoption of Building Information Modeling (BIM) allows digital simulation of connections and clashes before production, which is critical for reducing errors during assembly.



### **2.Factory Production**

Once designs are finalized, production begins in a controlled facility where:

Formwork and molds are prepared based on specified dimensions.

Reinforcement (steel bars, prestressing strands) is placed precisely within molds.

Concrete mixing uses engineered proportions tailored for performance, including admixtures for strength, durability, or rapid curing.

Casting and curing occur under controlled temperature and humidity conditions to ensure uniform strength development and surface quality.

The controlled environment of a precast plant minimizes environmental variability that can adversely affect concrete properties on a construction site.



### 3. Quality Control

Factory production enables robust quality assurance protocols. Precast plants employ consistent batching, standardized mix designs, and systematic testing (e.g., strength tests, dimensional checks) before elements leave the facility. This reduces the likelihood of defects such as honeycombing, improper curing, or inconsistent surface finishes commonly observed with on-site casting.

### 4. Transport and Handling

Precast elements are transported to the construction site using specialized vehicles and lifting equipment. Due to their size and weight, components often require route planning, permits, and protective packaging to prevent damages.



### 5. On-Site Assembly

Upon arrival, elements are positioned and secured using cranes, jacks, or temporary supports. Connection detailing is crucial — whether using bolted, welded, grouted, or hybrid systems — to ensure structural continuity and load transmission between members. Careful alignment and verification of tolerances are key steps before final connection closure.



## 6. Finishing and Integration

After structural assembly, additional works such as mechanical, electrical, and plumbing (MEP) integration, facade treatments, fireproofing, and insulation are completed. The precision of precast elements simplifies coordination with these systems, reducing on-site adjustments.

## Advantages of Precast Concrete Construction

Precast concrete offers several advantages compared to traditional cast-in-situ methods:

### 1. Quality and Precision

Because components are manufactured in a controlled factory environment, the concrete mix, curing conditions, and reinforcement placement can be closely monitored. This results in high consistency and uniformity in strength, durability, and surface finish. Factory quality control also reduces the number of defects and rework requirements on site.

### 2. Faster Construction Schedules

Precast elements are ready for assembly upon arrival at the construction site, allowing foundation work and other preparatory tasks to proceed concurrently with precast production. Eliminating on-site casting and curing delays dramatically shortens overall project timelines, which is especially valuable for large commercial or public infrastructure projects.

### 3. Cost-Effectiveness

Although initial costs for molds, plant setup, and logistics may be higher, overall project costs often decrease due to reduced labor, minimized waste, and shorter on-site durations. For repetitive or large-scale projects, cost savings can be significant.

### 4. Material Efficiency and Waste Reduction

Precast facilities accurately measure and control material usage, which minimizes waste. Compared to cast-in-situ construction — which often generates excess waste from formwork and on-site adjustments — precast systems promote sustainability and resource efficiency.

### 5. Improved Durability and Performance

Precast concrete elements are often designed for enhanced durability, including improved resistance to weathering, corrosion, and other environmental stresses. Their dense composition and factory cures contribute to long-term performance and reduced maintenance needs.

### 6. Reduced On-Site Labor

By relocating much of the labor to a manufacturing environment, precast construction reduces the need for highly skilled on-site labor, which is beneficial in regions facing labor shortages or safety risks associated with high-rise or infrastructure projects.

### 7. Sustainability

Factory production results in lower onsite waste and emissions. Precast elements also allow integration of energy-efficient designs, such as high thermal mass for passive temperature regulation, contributing to green building standards and reduced operational energy use.



## Disadvantages and Limitations

While precast concrete provides many benefits, it also has certain limitations that engineers and architects must consider:

### 1. High Initial Investment

Precast systems require investment in production plants, molds, and transport equipment. This cost can be prohibitive for small or one-off projects, making traditional cast-in-situ methods more economical in those contexts.

### 2. Transportation and Logistics

Transporting large precast components can be costly and complicated, particularly in urban or remote areas with limited access or low truck weight limits. Logistics planning must account for permits, route restrictions, and safety considerations.

### 3. Limited Flexibility for Site Changes

Because precast elements are manufactured in advance, last-minute design changes are difficult and costly once production has begun. This lack of adaptability can be a disadvantage compared to cast-in-situ methods that allow on-site modifications.

### 4. Joint and Connection Challenges

Precast systems introduce multiple joints that require careful detailing to ensure structural continuity and resistance to loads, including seismic or wind pressures. Poor joint design can compromise performance and increase maintenance needs.

### 5. Skill Requirements

Although on-site labor is reduced, precast construction demands specialized skills in production, transportation handling, and assembly. In regions lacking qualified technicians, this can hinder successful deployment.

## Comparative Analysis: Precast vs Cast-in-Situ Concrete

Criteria	Precast Concrete	Cast-in-Situ Concrete
Production Location	Off-site factory	On-site
Quality Control	High, controlled	Variable, site conditions
Construction Speed	Faster	Slower due to curing
Labour Demand	Lower on-site	Higher on-site
Flexibility	Limited on-site changes	High
Cost	Higher initial, lower lifecycle	Lower initial, higher on-site
Waste Generation	Minimal	Higher
Environmental Impact	Lower waste, often efficient	More site emissions

Precast excels in controlled production and schedule efficiency, while cast-in-situ supports bespoke designs and highly customized structural forms. Depending on project scale, timeline, and design complexity, professionals must choose the most suitable method.

## **USES OF PRECAST CONCRETE CONSTRUCTION IN DIFFERENT SECTORS**

### **1. Residential and Commercial Buildings**

Precast concrete has been widely adopted in residential and commercial projects due to its speed and precision. Components such as wall panels, floor slabs, beams, and columns are manufactured off-site, enabling rapid assembly and minimized disruption at urban sites. In housing developments where repetitive units are common, precast systems significantly improve productivity and delivery timelines.

### **2. Infrastructure Projects**

Precast concrete elements are heavily used in infrastructure, including bridges, viaducts, and tunnels. Highway authorities in some countries have mandated precast components for non-critical structures to enhance efficiency and reduce construction delays. In India, for example, the Ministry of Road Transport and Highways has directed the use of precast elements in suitable highway projects to streamline execution.

The Economic Times

### **3. Industrial and Public Works**

Large industrial facilities and public buildings benefit from precast systems due to their durability and low maintenance requirements. Precast concrete's high resistance to fire, corrosion, and other environmental stresses makes it desirable for long-lived infrastructure assets.

### **Best Practices for Implementation**

To maximize the benefits of precast concrete, civil engineers and architects should consider the following best practices:

#### **1. Early Integrated Design**

Incorporate precast planning at the earliest design stages with multidisciplinary coordination to ensure compatibility of structural elements, connections, and MEP integration.

#### **2. Detailed Shop Drawings and BIM**

Use Building Information Modeling (BIM) and detailed shop drawings to identify clashes, coordinate tolerances, and simulate assembly sequences before production begins.

#### **3. Quality Control Protocols**

Implement strict quality control measures at the precast facility, including standardized testing of concrete strength, dimensions, and surface integrity.

#### **4. Logistics Planning**

Develop logistics plans that account for transport routes, handling equipment, crane capacities, and safety protocols to prevent damage and delays.

#### **5. Training and Skill Development**

Invest in training for personnel involved in production, transportation, and assembly to ensure high competence and reduce on-site errors.

## **PRAGATI TOWERS – PRECAST CONCRETE HIGH-RISE CASE STUDY**

Location: Mumbai, India

Developers: L&T Realty and Omkar Realtors (JV)

Designer & Contractor: L&T Construction

Structural Consultant: Innovela Building Solutions

Review Consultants: Dr. Kelkar Consultants Pvt. Ltd. & Prof. A. Meher Prasad (IIT Madras)

## Project Overview

Pragati Towers is India's first total precast high-rise residential development. The project consists of eleven towers, each rising 70 m (G+23 floors) and comprising 300+ apartments per tower. The total built-up area for all towers is approximately 2.6 million sq ft.

The project is divided into Phase 1 (six towers) and Phase 2 (five towers). Three towers of Phase 1 are completed, while three are under construction. The buildings in Phase 1 share identical floor plans, which made full precast construction technically and economically feasible. Precast structural elements were used from the 1st to 23rd floor, with around 40,000 precast members installed.

Each apartment has a compact 269 sq ft carpet area, planned for EWS housing, consisting of a small living area, study, kitchen, and toilet-bath unit. Large-panel precast shear walls form the main structural frame.

The project was developed by Larsen & Toubro Realty Limited and Omkar Realtors & Developers Private Limited Joint Venture. The project was designed and constructed by Larsen and Toubro Construction (L&T Construction).

Table1-PragatiTowers –Phase1Project Details

PragatiTowers-Phase1–SixHigh-riseBuildings	
OverallBuiltUpArea	1.2millionsquare feet
StructuralFrame	G+ 23 Levels
TotalApartments	2024Apartments;14-16ApartmentsperLevel
StructuralSystem– Superstructure	LargePanelPrecastShear Walls
StructuralSystem-Substructure	PileFoundationorRaft Foundation
GroundandTerraceWork	CastInSitu
1 <sup>st</sup> to23 <sup>rd</sup> Floor Work	PrecastMembers
TotalPrecastMemberCount	~ 40,000



Fig.4 Pragati Towers –Overall Phase1 Layout



A typical apartment floor plan is shown in Figure 5. Each apartment comprising of 269 squarefeet of carpet area, consists of a living room, a study room, and a kitchen along with toilet and bath units, planned for typical EWS family of four. Figure 6 shows the precast panel layout used for the project.




Fig.5 Pragati Towers-Typical Apartment Floor Plan



Fig.6 Pragati Towers-Precast Panel Layout for the Typical Apartment Floor Plan

## DESIGN CONSIDERATIONS

### Design Codes

The design followed relevant Indian Standards:

IS 456-2000 – Concrete structures

IS 1893-2002 – Earthquake design

IS 13920-1993 – Ductile detailing

IS 11447-1985 – Large panel prefab guidelines

IS 15916-2010 – Design & erection of precast concrete

### **Design philosophy**

As precast technology was used for the first time for a high-rise residential structure in India, the emulative design philosophy was selected based on mutual agreement between the Client, Consultant and Contractor. Onsite, wet grouted joints for horizontal and vertical connections between walls and in-situ concrete joints for slab-to-wall and slab-to-slab joints, termed as “stitched” joints were selected. ETABS software was used to build the structural model for analysis. Various modeling approaches were considered and compared to come up with the design forces at all joints in the structure. The completed design approach is not in the scope of this paper. However, the various options considered have been compared by Dr. M. Prasad et al. (2013)<sup>11</sup>.

### **Design of connections**

#### **Horizontal Connections–Wall-to-Wall Connections**

All vertical walls with a few exceptions were treated as Shear Walls. Vertical connections transferred tension load at several locations even in the presence of several shear walls and relatively significant dead load on all walls. Continuous non-contact lap spliced dowel system using corrugated dowel tubes was selected to provide continuity in the vertical dowels. Non-shrink and non-metallic grout was used to fill the dowel tubes after lapping the dowels. The same grout was also targeted to fill the horizontal stacked wall-to-wall joints during the dowel tube grout filling activity. As a conservative approach, all dowels in the wall-to-wall joints (provided for tension as well as shear forces at joint) were continued throughout the height of the building for the completed buildings. Figure 7 shows the typical vertical stacked wall dowel connection.

#### **Horizontal Connections–Wall-to-Slab Connections**

During erection, the slab was supported by the bearing wall and temporary shoring. The slab and wall were then stitched together on-site to have emulative wall-slab joint. Figure 7 shows the typical wall-slab joint. Notched half-slab concept was used to limit on-site pour volume. As a conservative approach, the slab was designed as a simply supported slab. All slab-wall joints were detailed such that the in-situ stitching pour connected the members without any gaps in between to achieve emulative behavior. Necessary reinforcement per the prevalent code requirements was provided in the stitched joint. High flow concrete with one grade higher compressive strength than the compressive strength of the precast panels to be connected was used in the stitched joint.

#### **Vertical Connections–Wall-to-Slab Connection**

All wall panels were connected together at vertical joints as well to achieve emulative behavior. For erection feasibility, where the panels had to be erected vertically down to make the projected dowel connections, flexible wire loop shear key connectors were used across the vertical joints. Figure 8 shows the typical vertical wall-to-wall connection used. Adjacent shear key connectors at a joint were looped together using continuous rebar placed on-site. The joint was then grouted using non-shrink and non-metallic grout to seal it.




Fig.7 Pragati Towers–Typical Wall-to-Wall Dowel & Wall-to-Slab“Stitched”Joint Connection




Fig.8 Pragati Towers–Typical Wall-to-Wall Vertical Loop Connection

## PROJECT PLANNING AND OPERATIONS

### Preliminary production and erection planning

Due to the size of the project and other logistics and available transportation infrastructure constraints, two dedicated site-based factories were established - one next to the site for large members, and another about 10 km from the site for the balance production. Due to limited available site storage space, overall production rate was back calculated such that minimal surplus stock was stored at site. Due to the temporary nature of the production facilities and relatively small sized panels based on the floor plan, all members were designed as conventionally reinforced precast members instead of prestressed components. Due to scarcity of heavy-duty tower cranes in India, precast panel weight was kept under 6 tons (~13 kip). Figure 10 shows the precast panel layout. Most members were designed to be flat panels with a few exceptions such that majority of the production could be planned on flat beds or battery molds. To control costs, all molds were indigenously made instead of importing molds. Steel molds dedicated to individual panel type (all fixed side rails) were used considering high pour repetition.




Fig.10PragatiTowers–TypicalPrecastPanelLayout

## Site logistics and transportation planning

The city of Mumbai, known as the financial capital of India, is always busy and bustling. Congested roads leading to extended travel times in peak hours are not an uncommon sight. The project site for Pragati Towers, located in the heart of the city, was no exception. Thus, site based dedicated factories were preferred contrary to global practice of centralized factories. Figure 11 shows a bird's eye view of the site entrance. Detailed trailer movement and space optimization studies were carried out to calculate maximum number of trips per day for the trailers coming from site and the nearby off-site factory.



Fig. 11 Pragati Towers Phase1Site

## FABRICATION, STORAGE AND HANDLING

At both factories, predominantly battery molds were planned for panels with minimal opening and inserts; flat beds were planned for the remaining panels and indigenously built operable full height 3D molds were used for the toilet and bath units. The Client had some reservations regarding joint details with respect to water leakage. Thus the toilet and bath units were cast monolithically as a single 3D unit in order to avoid panel joints. Considering high mold repetition, all molds were built using steel plates. With the same consideration, individual molds were made for each member with member specific geometry to reduce preparation time. Thin foam pads were used in between the rail and flat bed joints to prevent slurry loss and achieve finished edges. Mold release oil was applied per international standard practices. Rebar cages were prefabricated for all molds. High flow concrete with high early strength concrete mix was selected that needed minimal vibrations. Plate vibrators and needle vibrators were used as required. Manual, concrete bucket, delivery system was selected to control operating costs. Mumbai climate is typically warm through the year with high relative humidity. Thus, initial wet curing followed by majority of air curing was selected instead of accelerated curing. All members were stored per the design intent (walls vertical and slabs horizontal) except the wall panels that were cast in flat beds. Due to limited availability of storage space, fabrication was planned in a just-in-time manner so that only limited stock was in excess. The site activities were planned for minimal storage and most panels were lifted off directly from the truck trailers to the building. Traditional 40 feet trailers were used. For Battery Mold panels, special A frames were prepared for vertical transportation. Figure 12 shows a few photos of the overall fabrication process adopted.





FlatBedMold



BatteryMold



StorageYard



PanelTransportation



Fig.12PragatiTowers–FabricationandTransportationActivities

## Erection planning

Heavy duty tower cranes with tip capacity ranging from 4-6 ton (8.8-11 kip) with a tip radius of 40-50 m (~ 130-164 ft) were selected. Due to close proximity of the buildings (8-10 m (~ 26-33 ft)) the cranes were positioned such that the crane radii did not interfere with each other. Tower A crane was selected with a luffing job to prevent interference with the adjacent crane. Depending on the schedule, at times adjacent tower cranes were used to erect portions of other towers. Typical erection was sequenced from one end of the building to the other end, going up level by level. Grouting of vertical connection dowels was followed immediately after the slabs were erected and the stitching activity was completed within one day of erection. All members were braced for a minimum of two levels below the working floor. On an average, around 50 panels were erected per crane per day. Overall the erection pace translated to 5 flats per day on an average and 10 flats per day at peak for the work of three towers. Precast work of all three towers was completed just under 11 months. Figure 13 shows the overall erection plan for individual buildings along with a photo of erection in progress.



Fig.13PragatiTowers–Erection Progress



## Finishing Works

Exterior faces were mold-finished and required only painting. Interior surfaces received primer and paint, avoiding traditional plaster, saving time and labor. Electrical conduits and plumbing lines were intentionally left exposed per client preference.



Outside Corridor & apartment interior

## CHALLENGES AND SOLUTIONS

### 1. Technology Acceptance

As precast high-rise construction was new in India, the client and consultants initially had reservations. Acceptance improved after reviewing global case studies with similar requirements in architecture, seismic design, and logistics.

### 2. Design Approach Adaptation

Global jointed construction systems were not adopted directly. Instead, emulative detailing was chosen to align with Indian construction practices and available skills. Mock-ups and load tests helped refine connection details.

### 3. Connection Material and Cost Constraints

Imported sleeve connectors were avoided due to strict tolerances and high costs. Instead, cost-effective local solutions like loop connectors, lap-splice dowels, and notched half-slabs were adopted.

### 4. Infrastructure Limitations

Unlike developed countries where centralized precast plants serve wide regions, India's road limitations led to the need for site-based factories, solving transportation obstacles.

## 5. Mold and Production Decisions

Indian factories usually do not have large long-line beds. Hence, member-specific steel molds were produced for repetitive high-volume casting.

Overall,

Pragati Towers demonstrates the successful implementation of total precast technology for high-rise residential construction in India. Through collaborative planning, adaptive design strategies, on-site factories, and meticulous production-erection coordination, the project overcame limitations related to transportation, local workmanship, and seismic considerations. The project serves as a pioneering model for future Indian precast high-rise developments.

## CONCLUSION

Precast concrete construction offers a powerful alternative to traditional cast-in-situ methods, delivering high consistency, improved quality, faster construction schedules, and enhanced sustainability. Although initial costs and logistical complexities present challenges, thoughtful planning, integrated design practices, and adherence to quality standards can unlock significant advantages for large-scale and repeated construction projects. By integrating modern tools such as BIM, robust quality control, and supply chain optimization, precast concrete is well positioned to play a central role in the future of civil engineering and architectural construction. Project teams should adopt best practices that prioritize early coordination, effective logistics, and continuing education to fully realize the benefits of precast methodologies.

## REFERENCES (LINKS ONLY)

<https://constructionhow.com/precast-concrete-vs-cast-in-situ-concrete/>

constructionhow.com

<https://concreterepairspecialists.uk/the-pros-and-cons-of-precast-concrete-construction/>

concreterepairspecialists.uk

<https://ph01.tci-thaijo.org/index.php/lej/article/view/256967>

Thai Journal Online

<https://www.precastconcretemagnet.com/info/boosting-productivity-precast-concrete-vs-cas-93186918.html>

Great Magtech (Xiamen) Electric Co.,Ltd

<https://precastbuildcon.com/why.html>

Precast Buildcon

<https://www.epcworld.in/precast-concrete-accelerating-construction/>

epcworld.in

<https://viralrang.com/advantages-of-using-precast-concrete/>

Viral Rang

[https://www.pci.org/PCI/PCI/Design\\_Resources/Sustainability\\_Resources/Frequently\\_Asked\\_Questions.aspx](https://www.pci.org/PCI/PCI/Design_Resources/Sustainability_Resources/Frequently_Asked_Questions.aspx)

PCI

<https://www.mdpi.com/2351556>

MDPI

[https://www.ijiset.com/vol3/v3s5/IJSET\\_V3\\_I5\\_34.pdf](https://www.ijiset.com/vol3/v3s5/IJSET_V3_I5_34.pdf)