International Journal of Scientific Research in Engineering and Management (IJSREM)
Volume: 10 Issue: 10 | Oct - 2026 SJIF Rating: 8.659 ISSN: 2582-3930

Smart Water Leakage Detection & Analytics Platform

[1]FRANKLIN F , [1]GOKULNATH R, [1]KIYAZ MOHAMED S [2] MANI P

[1]Student,[2] Assistant Professor
Department of Electronics and Communication Engineering
K.Ramakrishnan College of Technology, Trichy,Tamilnadu, India.

Abstract : Water leakage in underground and distribution pipelines can lead to significant water loss, property damage, and increased maintenance costs. Early identification of leakage is therefore important for utilities, industries, and other organizations responsible for water distribution. This paper presents the concept of a Smart Water Leakage Detection & Analytics Platform that combines Internet of Things (IoT) sensors, a field gateway, cloud analytics, and a monitoring interface. Flow, pressure, and acoustic sensors collect complementary information about pipeline behaviour. An IoT gateway pre-processes the measurements and transmits them through communication technologies such as LoRaWAN, NB-IoT, or Wi-Fi to a cloud analytics engine. The engine compares incoming readings with expected operating patterns and identifies deviations that may indicate a leak or abnormal pressure. Alerts can then be presented to operators through a web dashboard and mobile application. Where suitable hardware and confirmation logic are available, a smart shut-off valve can be used to isolate the affected pipeline section. The platform is intended to support continuous monitoring, faster investigation, historical reporting, and more efficient water management. The supplied project description does not provide measured field-test results; therefore, detection accuracy and actual water savings must be validated through implementation and experimental evaluation.

Keywords: Smart Water Monitoring, Internet of Things, Pipeline Leakage, Flow Sensor, Pressure Sensor, Acoustic Sensor, Cloud Analytics, Anomaly Detection, Smart Shut-off Valve.

INTRODUCTION

Water distribution infrastructure supports households, public services, commercial activity, agriculture, and industrial production. A large pipeline network may include underground pipes, joints, valves, storage facilities, and pumping equipment. A fault at any of these points can result in water loss and may remain unnoticed until a visible sign appears or a routine inspection is conducted. Leakage can also affect pressure in neighbouring pipe sections and may cause damage to nearby roads, buildings, or other infrastructure.Traditional monitoring often relies on periodic inspection, manual reports, or measurements taken at a limited number of locations. Such approaches can make it difficult to identify a leak quickly, particularly when the leak is underground or occurs in a location that is not frequently inspected. A continuous monitoring system can provide more frequent observations and help operators identify unusual conditions for further investigation.Embedded systems and IoT technologies provide a way to connect physical sensors with communication networks and software platforms. Sensors measure conditions in the field, a gateway collects or pre-processes the readings, and a cloud service stores and analyses the data. A dashboard can then present current values, historical trends, and alerts in a form that supports operational decisions. In the proposed project, flow, pressure, and acoustic measurements are used together because each describes a different aspect of pipeline behaviour.The Smart Water Leakage Detection & Analytics Platform is intended to combine these measurements with anomaly detection and operator notifications. It also considers optional automated valve control. The purpose is not to replace inspection and maintenance, but to help direct attention to pipeline sections that show unusual behaviour and may require confirmation.

PROBLEM IDENTIFICATION

Undetected leakage wastes treated water and can increase the cost of water production, pumping, treatment, and distribution. When a leak continues for a long period, the total water loss can become substantial. The fault may also lower pipeline pressure, disturb service to consumers, and create maintenance work that could potentially have been reduced through earlier detection.

A second challenge is that individual sensor readings can be ambiguous. A change in flow may result from normal demand variation as well as leakage. A pressure drop may be associated with a leak, but it may also occur during valve operation or other changes in the network. Acoustic measurements can contain background noise from pumps, traffic,

and surrounding activities. For this reason, a useful monitoring platform should consider more than one type of measurement and should present potential faults as alerts that can be reviewed. A further problem is the delay between observing a fault and informing the responsible operator. A connected dashboard and notification mechanism can make current sensor information easier to access. The proposed system therefore focuses on continuous data collection, anomaly identification, alert presentation, and optional shut-off control where the fault has been sufficiently confirmed.

OBJECTIVES

- To monitor pipeline conditions continuously for possible leakage.
- To collect flow, pressure, and acoustic measurements from selected pipeline locations.
- To use an IoT gateway to collect and transmit sensor information to a cloud analytics platform.
- To identify abnormal sensor patterns that may indicate leakage or an abnormal pressure condition.
- To notify operators through a web dashboard and mobile application.
- To support historical data review and reporting for maintenance planning.
- To provide an optional mechanism for commanding a smart shut-off valve after a leak is confirmed.
- To support water conservation and reduce avoidable maintenance and operating costs.

REVIEW OF EXISTING APPROACHES AND RESEARCH GAP

Pipeline monitoring methods include manual inspection, flow-based monitoring, pressure-based monitoring, acoustic sensing, and IoT-based systems. Manual inspection requires human effort and may delay leak detection, while flow and pressure sensors can identify unusual changes but may not always distinguish leakage from normal pipeline operations. Acoustic sensors detect sounds and vibrations associated with possible leaks, but background noise can affect their accuracy. IoT-based monitoring enables continuous data collection and remote monitoring, while cloud analytics helps analyse sensor readings and generate alerts. However, existing approaches may face challenges such as limited continuous monitoring, false alarms, unreliable communication, and difficulties in analysing multiple sensor readings. The research gap is the need for an integrated and scalable system that combines flow, pressure, and acoustic sensors with an IoT gateway and cloud analytics for effective leak detection. The proposed Smart Water Leakage Detection and Analytics Platform addresses this need by continuously monitoring pipeline conditions, identifying abnormal sensor patterns, and notifying operators through a web dashboard and mobile application. It also supports optional smart shut-off valve control after a leak is confirmed. Further testing is required to evaluate the system's detection accuracy, reliability, and effectiveness in reducing water wastage.

.

PROPOSED SYSTEM ARCHITECTURE

The proposed architecture is organized into sensing, gateway, communication, cloud processing, application, and actuation layers. This separation allows the field devices to collect data while the cloud service manages longer-term storage, analysis, reporting, and user-facing information. The exact hardware and network configuration can be adapted to the scale and connectivity available at the deployment site.

Sensing layer : Flow sensors measure the volume or rate of water moving through a pipe. Pressure sensors measure hydraulic pressure at selected points. Acoustic leak sensors capture sound or vibration signatures that may be associated with leakage. The project component list also includes a water quality sensor, which can provide additional monitoring information if it is incorporated into the final implementation. Sensor readings should be timestamped and associated with a known monitoring location.

IoT gateway: The IoT gateway receives readings from the field sensors and may perform basic checks such as range validation, timestamping, filtering, and formatting. The project lists an ESP32 as the gateway/controller option. The final gateway design should be selected according to the sensors' interfaces, power requirements, communication range, and deployment environment. Missing or implausible readings should be flagged rather than silently treated as normal.

Communication layer : The project proposes LoRaWAN, NB-IoT, or Wi-Fi as possible communication technologies. LoRaWAN may be suitable for low-data-rate sensor messages over a wider area when a compatible network is available. NB-IoT can be considered where cellular IoT service is supported. Wi-Fi may be practical at sites with reliable local wireless coverage. The final choice depends on coverage, power consumption, data frequency, cost, and infrastructure availability.

Cloud analytics layer : A cloud service receives and stores sensor data through a dataingestion API. A time-series database can organize readings by sensor and timestamp, allowing recent values and historical trends to be reviewed. The analytics engine compares current measurements with expected patterns and checks for deviations such as unusual flow variation, pressure drops, or abnormal acoustic signatures. The presentation proposes machine-learning-based analysis; the specific model, training data, and performance metrics remain implementation decisions.

Application and actuation layer : The web dashboard and mobile application display sensor status, trends, and alerts. Operators can review a warning, identify the affected zone, and arrange an inspection. If the system includes a compatible smart valve, control logic may issue a shut-off command after the leak is confirmed. Safety checks, manual override, communication-loss handling, and a record of valve commands should be considered before automated control is deployed.

WORKING PRINCIPLE AND METHODOLOGY

The proposed methodology for the Smart Water Leakage Detection and Analytics Platform begins with the installation and configuration of flow, pressure, and acoustic sensors at selected locations within the pipeline network to monitor water movement, pressure variations, and unusual sounds or vibrations associated with potential leakage. These sensors continuously collect measurements or operate at a predefined sampling interval, with each reading associated with a timestamp and sensor identifier to support accurate tracking and analysis. The collected data is then sent to an IoT gateway, such as an ESP32-based controller, where basic validation and preprocessing are performed to identify missing, invalid, or inconsistent readings and prepare the data for transmission.

The processed sensor data is transmitted through a suitable communication network, such as Wi-Fi, LoRaWAN, or NB-IoT, depending on the deployment environment, connectivity requirements, and communication range. At the cloud platform, the received measurements are stored in a time-series database, allowing current readings to be compared with historical data, expected operating conditions, and predefined threshold values. The system analyses the sensor measurements to identify abnormal patterns, such as unexpected changes in water flow, sudden pressure drops, or unusual acoustic activity, which may indicate a possible pipeline leak. Where data from multiple sensors is available, the readings can be correlated to improve the assessment and reduce false alarms; however, the exact detection logic and thresholds must be configured and evaluated for the specific pipeline network. When a potential leakage event is identified, the system records the event and displays relevant information on a web dashboard, including sensor readings, event time, and the affected monitoring point, while a notification is sent to the responsible operator for further investigation. The operator then reviews the available information and follows the defined operational procedure to confirm whether a leak has occurred before taking corrective action. If a smart shut-off valve is installed and the system is authorized to control it, the valve may be operated according to the confirmed event, predefined safety rules, and applicable operating conditions to limit further water loss. Throughout the process, sensor measurements, alerts, operator responses, and valve-control events are retained for reporting, system performance evaluation, maintenance planning, and future improvement of detection rules. The overall processing sequence consists of sensor measurement, gateway preprocessing, network transmission, cloud storage and analysis, anomaly identification, operator notification, and optional valve control. For reliable operation, the system must define suitable sampling intervals, acceptable sensor ranges, alert thresholds, communicationfailure handling, data-loss recovery procedures, and an escalation process based on the characteristics and requirements of the pipeline being monitored.

SYSTEM COMPONENTS

Flow sensor : The flow sensor provides information about the rate of water movement through the pipeline. Its readings can be compared over time or with measurements from other locations to identify unexpected variation. Selection and installation should account for pipe diameter, operating flow range, fluid conditions, and the sensor's measurement interface.
Pressure sensor : The pressure sensor measures the hydraulic pressure at a monitoring point. Sudden or sustained pressure changes may be useful indicators of abnormal pipeline behaviour. The sensor should be installed at a suitable location and calibrated for the expected pressure range. A pressure change alone should not automatically be considered proof of leakage because normal network operations can also change pressure.
Acoustic leak sensor : The acoustic sensor records sound or vibration associated with the pipe and its surroundings. A leak may produce a characteristic signal, but background noise and differences in pipe material or installation can affect the measurement. Signal processing and site-specific testing are needed before reliable decision thresholds can be set.
IoT gateway and cloud platform : The gateway links field measurements with the communication network. The cloud platform handles data ingestion, storage, analytics, and user-facing reporting. Together they provide the infrastructure needed to review both current conditions and historical behaviour. Secure communication, access control, reliable timestamps, and recovery from temporary connectivity loss should be considered in the implementation.

Smart shut-off valveA smart shut-off valve can isolate a section of pipeline when a confirmed leak requires immediate action. The presentation includes automated shut-off as a possible feature. Its implementation depends on the valve actuator, power supply, control interface, and the safety requirements of the network. A manual override and a clear event log are advisable so that operators can understand and manage the system's actions.

ALERT LOGIC AND DATA INTERPRETATION

An alert engine converts sensor measurements into events that operators can understand. A simple first version could use configured thresholds and rules, while a more advanced version could combine several features or use a machine-learning model. For example, a pressure drop occurring alongside an unexpected flow change and an unusual acoustic signature could be assigned a higher priority for investigation than a single isolated change. This is an illustrative decision rule, not a validated detection algorithm for the current project. Each alert should contain the affected sensor or zone, the time of detection, the readings that contributed to the event, and the recommended next action. Alerts should distinguish between a possible leak, a sensor fault, a high pressure condition, and a communication outage. Clear categories can help reduce confusion and make later review more useful . If machine learning is used, its performance should be evaluated with representative labelled examples of normal operation and known leak conditions. Relevant evaluation measures may include precision, recall, false-alarm rate, detection delay, and performance across different operating conditions. No measured accuracy value should be reported until the model has been tested with documented data.

DASHBOARD, MONITORING, AND REPORTING

The proposed web dashboard is the main interface for viewing pipeline conditions. It can show current flow and pressure values, acoustic status, water-quality readings when available, and the operational state of each sensor. Trend charts help users identify changes over time, while an alert panel highlights events requiring attention. The interface can also provide a table of recent sensor readings and a history of alerts. A mobile application can extend access to field operators and maintenance staff. Notifications may be used for potential leaks, high pressure, sensor disconnection, or low battery where the relevant hardware supports such monitoring. Historical reports can summarize event frequency, response times, sensor availability, and recurring problem locations. The exact dashboard functions should reflect the information actually available from the deployed hardware and software.

RESULTS AND DISCUSSION

The proposed Smart Water Leakage Detection and Analytics Platform is designed to provide continuous monitoring of pipeline conditions by integrating flow, pressure, and acoustic sensors with an IoT gateway and a cloud-based analytics platform. The system collects sensor readings at predefined intervals and transmits the processed data to the cloud, where the measurements can be stored, analysed, and compared with expected operating conditions. Changes in flow rate, sudden pressure drops, and unusual acoustic signals can be used to identify potential leakage events. By combining information from multiple sensors, the platform aims to improve leak assessment and reduce the possibility of false alarms compared with relying on a single sensor alone. The dashboard provides a central interface for viewing sensor readings, monitoring pipeline conditions, and identifying suspected leakage events, while notifications help operators respond promptly. If a smart shut-off valve is installed and authorised, it can support water-loss reduction by stopping the supply after a leak has been confirmed according to the defined safety procedures.



Figure : output image

The integration of IoT communication, cloud-based data storage, and multi-sensor analysis is expected to improve monitoring efficiency and support faster responses to suspected leaks. Previous studies have demonstrated the potential of acoustic signal analysis and IoT-based systems for detecting pipeline leakage under experimental or operational conditions. However, the proposed project's actual results must be confirmed through prototype testing. Evaluation should measure leak detection accuracy, false alarm rate, alert delivery time, communication reliability, and valve response where applicable. Tests should include normal water flow, different leak sizes, pressure variations, and communication interruptions to assess the system's reliability under different operating conditions. Overall, the proposed platform offers a practical approach to water pipeline monitoring, early leak identification, and water conservation, while further experimental validation is required to quantify its performance and effectiveness.

FUTURE ENHANCEMENTS

- Integrate GIS mapping so sensor locations and alerts can be associated with pipeline assets.
- Investigate deep-learning methods for predictive maintenance and more detailed anomaly analysis.
- Use solar-powered sensor nodes to extend deployments in locations with limited access to mains power.
- Enable automatic shut-off after a leak is confirmed, with appropriate safety interlocks and manual override.

- Integrate billing systems to compare usage patterns and provide consumer-usage insights where appropriate.
- Add stronger device authentication, encrypted communications, access controls, and audit logs.
- Develop a field-testing programme covering different pipe materials, flow rates, pressure ranges, and environmental conditions.

CONCLUSION

The Smart Water Leakage Detection & Analytics Platform proposes an IoT-based method for monitoring pipeline conditions using flow, pressure, and acoustic sensors. Sensor data is collected through a gateway and transmitted to a cloud analytics engine, where unusual patterns can be flagged for operator review. A web dashboard and mobile application provide a means of viewing current conditions, alerts, and historical readings. Optional smart shut-off valve control can provide a response mechanism when a leak is confirmed and the necessary hardware is available.

The modular architecture is relevant to municipal distribution, smart-city infrastructure, industrial pipelines, and agricultural water systems. It offers a practical basis for further development, but its operational value must be established through systematic testing. Future work should focus on sensor calibration, anomaly-detection validation, communication reliability, safe valve operation, and measurement of actual water and cost outcomes.

REFERENCES

[1] X. Wan, P. Khorsandi Kuhanestani, R. Farmani, and E. Keedwell, "Literature Review of Data Analytics for Leak Detection in Water Distribution Networks: A Focus on Pressure and Flow Smart Sensors," Journal of Water Resources Planning and Management, vol. 148, no. 10, 2022.

[2] A. W. Z. Chew, Z. Y. Wu, R. Kalfarisi, X. M. Meng, and J. Pok, "Generalized Acoustic Data Analysis Framework for Leakage Detection and Localization in Field Operational Water Distribution Networks," Journal of Water Resources Planning and Management, vol. 149, no. 11, 2023.

[3] H. Fan, S. Tariq, and T. Zayed, "Acoustic Leak Detection Approaches for Water Pipelines," Automation in Construction, 2022.

[4]"An IoT Based Pipeline Management and Leakage Detection System," in Proceedings of the 2024 IEEE 9th International Conference for Convergence in Technology (I2CT), 2024.

[5] "IoT and GIS Based Real Time Water Pipeline Surveillance and Leak Detection System," in Proceedings of the 2024 International Conference on Smart Electronics and Communication Systems (ISENSE), 2024.

[6] "Review of Model-Based and Data-Driven Approaches for Leak Detection and Location in Water Distribution Systems," Water Supply, vol. 21, no. 7, pp. 3282–3306, 2021.

[7] "Leak Detection and Localization in Water Distribution Networks Using Conditional Deep Convolutional Generative Adversarial Networks," Water Research, vol. 238, article 120012, 2023.

[8] "Artificial Intelligence in Water Distribution Networks: A Systematic Review of Models, Input Variables, Databases, and Output Strategies for Leak Detection," Smart Cities, vol. 9, no. 3, article 45, 2026.

[9] "Towards Achieving a Reliable Leakage Detection and Localization Algorithm for Application in Water Piping Networks: An Overview," IEEE Access, vol. 5, pp. 20272– 20291, 2017.

[10] "A Pressure-Based Method for Monitoring Leaks in a Pipe Distribution System: A Review," Renewable and Sustainable Energy Reviews, vol. 69, pp. 902–911, 2017.