

STUDY ON BEHAVIOUR OF DIAGRID STRUCTURE FOR DIFFERENT DIAGRID ANGLES WITH CONSTRUCTION SEQUENCE ANALYSIS

Mr. Nagaraja S N¹, Mr. Sunny K²,

¹Student, Master of Technology, Department of civil engineering, East West Institute of Technology, Bangalore.

²Assistant Professor, Department of civil engineering, East West Institute of Technology, Bangalore.

Abstract - It is frame work of diagonally intersecting metal, concrete, or wooden beams i.e. used in the construction of building and roofs and its diagonal components can carry both gravity and lateral loads due to their triangulated design and axial actions. Construction sequence analysis is a non linear analysis approach in which the structures in analyzed at various stages corresponding to the construction sequence and partially required loads are applied sequentially at every stage. A plan of 20 m × 20m size was considered. ETABS 2016 was used in modeling and analysis of structural members and subjected to seismic loads for zone V as per IS1893-2016. In total 6 models with different diagrid angles (52° 62° & 68°) and column removal scenario at different floor levels. To study bending moment and shear force variation in transfer girder beams for with and without construction sequence and study axial force variation in columns for with and without construction sequence analysis & also study seismic response of diagrid structure with different diagrid angles i.e., storey displacement and storey drift. For response spectrum analysis when compared different diagrid models (62° and 68°), diagrid model 68° is less displacement as compared to other degrees implying that we take above 68° diagrid angle is best for tall buildings. A more realistic design than the standard design is produced by including sequential load case in the study of multistory RCC structure.

Key Words: Diagrid angle, construction sequence analysis,

1. INTRODUCTION

India is one of the countries where the majority of structures are low-rise, although industrialization has resulted in population growth in most of the cities. To accommodate those individuals in a small location, the building's height needs be increased from medium to high. Improper design and construction of all types of residential structures causes widespread structural deterioration throughout the world. As a result, we must emphasize structure safety over cost savings. From both a design and a safety standpoint, the structure should be created in such a way that it is both safe and inexpensive. Wind and earthquakes both have dynamic effects on structures; however wind force and earthquake design should be considered separately.

Diagrid has developed as a new tall-building design concept. The main distinction between diagrid structures and

traditional outside braced frame constructions is that diagrid structures do not have any vertical columns. The diagrid system is possible because diagrid structures' component diagonals they are able to support lateral and gravitational stresses because of their triangular shape. When compared to typical framed tubular structures without diagonals, diagrid construction transfers load through axial action and lowers shear deformation, whereas traditional framed tubular structures transfer shear through vertical column bending

Construction sequence analysis is a non linear analysis approach in which the structures in analyzed at various stages corresponding to the construction sequence and partially required loads are applied sequentially at every stage. The purpose of this study is to investigate the change in values of numerous structural parameters namely axial force, shear force, and bending moment during and after construction.

Types of Diagrid Structural System

1. Steel diagrid structural system
2. Concrete diagrid structural system
3. Timber diagrid structural system

Concrete diagrid structural system in which the versatility of the precast concrete components may allow them to precisely suit the layout of the construction. It also offers fire suppression systems. Precast concrete, but in the other end, makes a greater contribution to the dead load of the building.

OBJECTIVES

1. To study the effect of construction sequence analysis on diagrid structure with different diagrid angles using etabs.
2. To study bending moment and shear force variation in transfer girder beams for with and without construction sequence.
3. To study axial force variation in columns for with and without construction sequence analysis.
4. To study seismic response of diagrid structure with different diagrid angles i.e., storey displacement and storey drift.

2. MODELLING AND ANALYSIS

In the present study, 6 models are considered, which are created using ETABS software, where in each model, 2 cases of column removal at ground floor and 12th floor locations are taken. The layout and elevation of a square building under consideration for study are both symmetric. The building to be modeled has a plan measurement of 20 m x 20 m.

TITTLE	Description
Structure	Concrete
Plan dimensions	20 m × 20 m
Number of stories	G + 25
Height of the structure	80 m
Floor height	3.2 m
Zone	Z-5
Concrete grade	M25 & M40
Steel grade	HYSD 500
Column size	750 × 750 mm
Beam size	300 × 600 mm 400 × 600 mm
Slab thickness	150 mm
Diagrid section	300 × 600 mm
Wall load (glass panels) 100mm	6.58 KN/m
Floor finish	1.5 kN/m ²
Live load	3 kN/m ²
Roof live load	1.5 kN/m ²

The maximum values of transferred girder moments, shear force and axial force are tabulated for (DL+LL) combination and construction sequence analysis (AUTO SEQ) for different position of floating columns at different stories.

Step by step procedure for analysis

MODEL 1: DIAGRID ANGLE: 52°0'5"

In RCC 52° diagrid building, bending moment, shear force of transfer girder and axial force variations in columns after removing at the centre of ground floor and mid floor column in the seismic zone 5 analysing for normal (DL+LL) combination and applying AUTO SEQ method.

MODEL 2: DIAGRID ANGLE: 52°0'5"

In RCC 52° diagrid building, bending moment, shear force of transfer girder and axial force variations in columns after removing at the corner of ground floor and mid floor column in the seismic zone 5 analysing for normal (DL+LL) combination and applying AUTO SEQ method.

MODEL 3: DIAGRID ANGLE: 62°29'17"

In RCC 62° diagrid building, bending moment, shear force of transfer girder and axial force variations in columns after removing at the centre of ground floor and mid floor column in the seismic zone 5 analysing for normal (DL+LL) combination and applying AUTO SEQ method.

MODEL 4: DIAGRID ANGLE: 62°29'17"


In RCC 62° diagrid building, bending moment, shear force of transfer girder and axial force variations in columns after removing at the corner of ground floor and mid floor column in the seismic zone 5 analysing for normal (DL+LL) combination and applying AUTO SEQ method

MODEL 5: DIAGRID ANGLE: 68°39'47"

In RCC 68° diagrid building, bending moment, shear force of transfer girder and axial force variations in columns after removing at the centre of ground floor and mid floor column in the seismic zone 5 analysing for normal (DL+LL) combination and applying AUTO SEQ method.

MODEL 6: DIAGRID ANGLE: 68°39'47"

In RCC 68° diagrid building, bending moment, shear force of transfer girder and axial force variations in columns after removing at the corner of ground floor and mid floor column in the seismic zone 5 analysing for normal (DL+LL) combination and applying AUTO SEQ method.






Fig 1. Elevation view of building with 4 locations where the columns are removed

BM FROM 52°, 62° AND 68° DIAGRID ANGLE BY REMOVING COLUMN @ THE CENTRE OF GF AND MID FLOOR

Moment of transfer girder after removing at the centre of ground floor and mid floor column in the seismic zone 5 analyzing for normal (DL+LL) combination and applying AUTO SEQ method.


SL NO.	POSITION OF TRANSFER GIRDER	BM WITHOUT AUTO SEQUENC E	BM WITH AN AUTO SEQUENC E	% OF VARIA TION
1	BM AT GROUND FLOOR TRANSFER GIRDER (KN-M)	347.07	688.88	98.47%
		339.67	660.68	94.50%
		337.62	644.42	90.87%
2	BM AT MID FLOOR TRANSFER GIRDER (KN-M)	266.32	683.49	156.6%
		262.25	654.27	149.4%
		260.90	646.10	147.6%

When compared to traditional analysis, auto sequence bending moment variation of ground floor level at the centre is 94.6% less as compared to auto sequence bending moment variation at mid floor level at the centre is 151.25%.


BM FROM 52°, 62° AND 68° DIAGRID ANGLE BY REMOVING COLUMN @ THE CORNER OF GF AND MID FLOOR

Moment of transfer girder after removing at the corner of ground floor and mid floor column in the seismic zone 5 analysing for normal (DL+LL) combination and applying AUTO SEQ method.

SL NO.	POSITION OF TRANSFER GIRDER	BM WITHOUT AUTO SEQUENC E	BM WITH AN AUTO SEQUENC E	% OF VARIA TION
1	BM AT GROUND FLOOR TRANSFER GIRDER (KN-M)	253.08	684.64	170.5%
		252.36	747.48	196.1%
		253.29	769.55	203%
2	BM AT MID FLOOR TRANSFER GIRDER (KN-M)	195.06	762.79	291%
		220.93	855.67	287%
		233.46	897.59	284.4%



When compared to traditional analysis, auto sequence bending moment variation of ground floor level at the corner is 189.90% less as compared to auto sequence bending moment variation at mid floor level at the corner is 287.49%.




SF FROM 52°, 62° AND 68° DIAGRID ANGLE BY REMOVING COLUMN @ THE CENTRE OF GF AND MID FLOOR

Shear force of transfer girder after removing at the centre of ground floor and mid floor column in the seismic zone 5 analyzing for normal (DL+LL) combination and applying AUTO SEQ method.

SL NO.	POSITION OF TRANSFER GIRDER	SF WITHOUT AUTO SEQUENC E	SF WITH AN AUTO SEQUENC E	% OF VARIA TION
1	SF AT GROUND FLOOR TRANSFER GIRDER (KN-M)	150.59	308.78	105%
		147.53	295.45	100%
		146.73	288.81	96.83%
2	SF AT MID FLOOR TRANSFER GIRDER (KN-M)	118.48	309.72	161%
		116.71	296.11	153.7%
		116.13	293.10	152.3%

SL NO.	POSITION OF TRANSFER GIRDER	SF WITHOUT AUTO SEQUENC E	SF WITH AN AUTO SEQUENC E	% OF VARIA TION
1	SF AT GROUND FLOOR TRANSFER GIRDER (KN-M)	61.86	164.63	166%
		61.72	177.20	187%
		61.91	181.62	193%
2	SF AT MID FLOOR TRANSFER GIRDER (KN-M)	50.26	180.26	258%
		55.43	198.84	258%
		57.94	207.23	257.6%




When compared to traditional analysis, auto sequence shear force variation of ground floor level at the corner is 182% less as compared to auto sequence shear force variation at mid floor level at the corner is 257.86%.

AF FROM 52°, 62° AND 68° DIAGRID ANGLE BY REMOVING COLUMN @ THE CENTRE OF GF AND MID FLOOR

Axial force of transfer girder after removing at the centre of ground floor and mid floor column in the seismic zone 5 analysing for normal (DL+LL) combination and applying AUTO SEQ method.

SL NO.	POSITION OF TRANSFER GIRDER	AF WITHOUT AUTO SEQUENC E	AF WITH AN AUTO SEQUENC E	% OF VARIA TION
1	AF AT GROUND FLOOR TRANSFER GIRDER (KN-M)	8714	12268	40.78%
		8415	12580	49.49%
		8326	12769	53.3%




When compared to traditional analysis, auto sequence shear force variation of ground floor level at the centre is 100.61% less as compared to auto sequence shear force variation at mid floor level at the centre is 155.69%.

SF FROM 52°, 62° AND 68° DIAGRID ANGLE BY REMOVING COLUMN @ THE CORNER OF GF AND MID FLOOR

Shear force of transfer girder after removing at the corner of ground floor and mid floor column in the seismic zone 5 analyzing for normal (DL+LL) combination and applying AUTO SEQ method.

2	AF AT MID FLOOR TRANSFER GIRDER (KN-M)	4919	6925	40.78%
		4703	7130	51.6%
		4635	7231	56%



When compared to traditional analysis, auto sequence axial force variation of ground floor level at the corner is 55.70% less as compared to auto sequence axial force variation at mid floor level at the corner is 62.13%.

STOREY DISPLACEMENT (X) and (Y)

SL NO.	MAXIMUM DISPLACEMENT @ DIFFERENT DIAGRID ANGLES	EQX (mm)	SPECX (mm)	% OF VARIATION
1	52°0'5"	86.40	54.36	58.94%,
2	62°29'17"	84.72	59.10	43.35%
3	68°39'47"	91.94	66.08	39%




Fig Difference between storey displacements in different diagrid angle @ X and Y

When compared to traditional analysis, auto sequence axial force variation of ground floor level at the centre is 47.85% less as compared to auto sequence axial force variation at mid floor level at the centre is 49.46%.

AF FROM 52°, 62° AND 68° DIAGRID ANGLE BY REMOVING COLUMN @ THE CORNER OF GF AND MID FLOOR


Axial force of transfer girder after removing at the corner of ground floor and mid floor column in the seismic zone 5 analyzing for normal (DL+LL) combination and applying AUTO SEQ method.

SL NO.	POSITION OF TRANSFER GIRDER	AF WITHOUT AUTO SEQUENCE	AF WITH AN AUTO SEQUENCE	% OF VARIATION
1	AF AT GROUND FLOOR TRANSFER GIRDER (KN-M)	9465	13842	46.24%
		9129	14395	57.68%
		9056	14788	63.2%
2	AF AT MID FLOOR TRANSFER GIRDER (KN-M)	5246	7871	50%
		4995	8226	64.68%
		4925	8457	71.71%

The displacement in model with ZONE 5 along X & Y direction for response spectrum analysis when compared different diagrid models 52°, 62° and 68°. is (58.94%, 43.35% and 39%). Therefore 68° diagrid model is less displacement as compared to other degrees.

STOREY DRIFT (X) and (Y)

SL NO	MAXIMUM DRIFT @ DIFFERENT DIAGRID ANGLES	DIFFERENT STOREYS	EQX	SPECX	% OF VARIATION
1	52°0'5"	17 th AND 17 th STOREY	0.001234	0.000802	53%
2	62°29'17"	14 th and 17 th STOREY	0.001201	0.000864	39%
3	68°39'47"	15 th and 15 th STOREY	0.001304	0.000967	34%



The drift in model with ZONE 5 along X & Y direction for response spectrum analysis when compared different diagrid models 52°, 62° and 68° is (53.86%, 39% and 34.85%). Therefore 68° diagrid model is less storey drift as compared to other degrees.

CONCLUSIONS

- When compared to traditional analysis, auto sequence bending moment, shear force and axial force variation of ground floor level at the centre is less as compared to auto sequence bending moment, shear force and axial force variation at mid floor level at the centre.
- When compared to traditional analysis, auto sequence bending moment, shear force and axial force variation of ground floor level at the corner is less as compared to auto sequence bending moment, shear force and axial force variation at mid floor level at the corner.
- The displacement in model with zone 5 along X & Y direction for response spectrum analysis when compared different diagrid models 52°, 62° and 68°. Therefore 68° diagrid model is less displacement as compared to other degrees
- The drift in model with zone 5 along X & Y direction for response spectrum analysis when compared different diagrid models 52°, 62° and 68°. Therefore 68° diagrid model is less storey drift as compared to other degrees.
- Building sequence analysis is required for RCC structures in order to increase the analysis & accuracy for displacement, axial, moment, and shear forces in nearby supporting beams and columns as well as for the entire structure.
- A more realistic design than the standard design is produced by including sequential load case in the study of multistory RCC structure.

REFERENCE

- Mulamreddy Sivareddy "Using ETABS, investigate and compare Construction Sequence Analysis with Conventional Lumped Analysis."(2021).
- Mohammad Afifuddin, Arvind B Vawhale "Analysis of Chronological Construction Sequences and Conventional Analysis in Comparison"(2020).
- Comparative Study on Construction Sequence Analysis on Steel Structure without and with Floating Columns," Tin Yadanar Kyaw and Nyein Nyein Thant (2019).
- Tin Yadanar Kyaw et al "study on the setback steel structure's construction sequence analysis is described" (2019).

5. Mohammed Affan et al "Comparative research of static and dynamic analysis of high-rise buildings in different seismic zones and diverse soil types (2018).
6. Jayesh Venkolath et al "study on different diagrid angles and to find the ideal diagrid angle for reducing horizontal slide & dislocation in a slightly raised building (2016)".
7. MV Naveen and KJ Brahma Chari (2016) "Study on Multi-Storey Building Static and Dynamic Analysis"
8. Rohit Kumar Singh (2014) In this study, a concrete diagrid building was created, investigated, and contrasted with a standard frame building.