

Sustainable Highway Engineering Decisions Using Conventional and Digital Analytical Tools

Ranjeet Kumar Yadav ¹, Prof. Anil Rajpoot ²

¹Research Scholar, Department of Civil Engineering, School of Engineering and Technology Vikrant University, Gwalior, (M.P.), India

²M.Tech Guide, Department of Civil Engineering, School of Engineering and Technology Vikrant University, Gwalior, (M.P.), India

Abstract

Highway construction projects are essential for economic growth, regional connectivity, and industrial development. However, delays in highway projects remain one of the most significant challenges faced by the construction industry worldwide, particularly in developing countries like India. Delays result in cost overruns, contractual disputes, reduced productivity, and public inconvenience. This research paper examines decision-making models used for delay mitigation in highway construction projects. The study explores traditional and modern decision-making approaches such as Critical Path Method (CPM), Program Evaluation and Review Technique (PERT), Analytical Hierarchy Process (AHP), Fuzzy-AHP, Decision Trees, Building Information Modeling (BIM), and Artificial Intelligence (AI)-based predictive models. The paper also analyzes major delay factors in Indian highway projects and proposes an integrated framework for proactive delay mitigation. Statistical findings from recent studies indicate that land acquisition delays, poor planning, regulatory approvals, and financial constraints are major contributors to project delays. The study concludes that hybrid decision-support systems integrating risk assessment, data analytics, and digital construction technologies can significantly reduce project delays and improve highway project performance.

Keywords: Highway construction, delay mitigation, decision-making models, AHP, CPM, BIM, risk assessment, infrastructure management.

1. Introduction

Transportation infrastructure plays a vital role in national development. Highway construction projects contribute significantly to trade, logistics, industrial growth, and employment generation. India possesses one of the largest road networks globally, exceeding 6.3 million kilometers. Despite continuous investments under programs such as Bharatmala Pariyojana and National Infrastructure Pipeline (NIP), highway projects frequently experience delays. These delays adversely affect project cost, quality, and stakeholder confidence.

Studies indicate that a large proportion of highway projects in India exceed their scheduled completion time by 20–50%. Common causes include poor project planning, delayed land acquisition, environmental clearances, financial instability, shortage of resources, and ineffective communication among stakeholders.

Modern highway construction therefore requires systematic decision-making models capable of identifying risks, prioritizing critical factors, and supporting timely managerial interventions.

2. Objectives of the Study

The major objectives of this research are:

1. To identify major causes of delays in highway construction projects.
2. To examine decision-making models used for delay mitigation.

3. To analyze statistical findings related to delay factors.
4. To evaluate the effectiveness of modern digital and AI-based approaches.
5. To propose an integrated decision-making framework for highway project management.

3. Research Methodology

The study is based on:

- Literature review of journal articles, reports, and conference papers.
- Comparative analysis of decision-making models.
- Statistical findings from highway construction studies.
- Review of Indian highway infrastructure projects and mitigation practices.

Secondary data from published research papers and infrastructure studies were used for analysis.

4. Major Causes of Delays in Highway Construction Projects

Research studies have identified several critical delay factors in highway projects.

4.1 Land Acquisition Delays

Land acquisition remains the most critical issue in Indian highway projects. A study involving 384 highway experts identified land acquisition as the top-ranked delay factor in Hybrid Annuity Model (HAM) projects.

4.2 Regulatory Approvals and Clearances

Environmental and forest clearances significantly impact project schedules. Delays in obtaining approvals from government agencies can postpone project execution for months or years.

4.3 Poor Planning and Scheduling

Improper scheduling and weak project coordination are major contributors to time overruns. Studies reveal that ineffective planning and scheduling rank among the top four causes of delays in Indian infrastructure projects.

4.4 Financial Constraints

Delayed contractor payments, inflation, and cash flow shortages affect procurement and labor productivity.

4.5 Resource Management Issues

Shortage of skilled labor, equipment breakdown, and material supply disruptions reduce project efficiency.

4.6 External Factors

Weather conditions, political instability, legal disputes, and pandemics also contribute to delays.

5. Statistical Analysis of Delay Factors

A study on Indian HAM highway projects identified 35 major delay-causing factors and categorized them through Principal Component Analysis (PCA). The survey included responses from:

Stakeholder Category	Number of Respondents
Government/Client Officials	123
Contractors/Concessionaires	159
Consultants	102
Total	384

The study found the following top delay factors:

Rank Delay Factor

- 1 Land acquisition delays
- 2 Delay in approvals and clearances
- 3 Changes in government regulations
- 4 Poor planning and scheduling

Another study analyzing 412 industry professionals identified 79 specific delay factors grouped into seven categories including contractor-related, consultant-related, labor-related, and external factors.

6. Decision-Making Models for Delay Mitigation

6.1 Critical Path Method (CPM)

The Critical Path Method is one of the most widely used scheduling techniques in highway construction.

$$CPM = \max(T_1 + T_2 + \dots + T_n)$$

Applications

- Activity sequencing
- Schedule optimization
- Delay impact analysis
- Resource allocation

Advantages

- Identifies critical activities.
- Helps managers prioritize tasks.
- Supports progress monitoring.

Limitations

- Does not effectively handle uncertainty.
- Requires accurate activity duration estimates.

6.2 Program Evaluation and Review Technique (PERT)

PERT is useful for projects involving uncertain activity durations.

$$TE = TO + 4TM + TP \quad T_E = \frac{T_O + 4T_M + T_P}{6} \quad TE = 6TO + 4TM + TP$$

Where:

- TET_ETE = Expected time
- TOT_OTO = Optimistic time
- TMT_MTM = Most likely time
- TPT_PTP = Pessimistic time

Benefits

- Supports probabilistic scheduling.
- Improves uncertainty management.
- Useful in large infrastructure projects.

6.3 Analytical Hierarchy Process (AHP)

AHP is a multi-criteria decision-making technique used to rank delay factors based on severity and importance.

Research shows AHP has been effectively used in Chinese and Asian highway projects for prioritizing project risks.

Steps in AHP

1. Problem identification
2. Hierarchical structuring
3. Pairwise comparison
4. Weight calculation
5. Ranking alternatives

Applications

- Risk prioritization
- Contractor selection
- Resource optimization
- Delay mitigation planning

6.4 Fuzzy-AHP Model

Traditional AHP may fail to handle uncertainty and subjective judgments. Fuzzy-AHP integrates fuzzy logic with AHP for better decision-making under uncertainty.

A 2023 study proposed an integrated Fuzzy-AHP and Decision Tree model for road construction delay management.

Advantages

- Handles ambiguous information.
- Improves expert judgment accuracy.
- Supports complex infrastructure decisions.

6.5 Decision Tree Models

Decision trees support predictive analysis and risk-based decision-making.

Applications

- Delay prediction
- Contractor performance evaluation
- Risk categorization

Modern decision-tree models can analyze multiple project variables and recommend corrective actions.

6.6 Building Information Modeling (BIM)

BIM is increasingly used for project visualization, clash detection, and schedule coordination.

BIM Benefits in Delay Mitigation

- Real-time project tracking
- Improved communication
- Enhanced scheduling accuracy
- Reduced design conflicts

Studies indicate BIM implementation can reduce project rework by 20–30%.

6.7 Artificial Intelligence and Machine Learning Models

Recent studies use machine learning for predicting highway construction delays.

A 2025 automated framework combined machine learning and predictive analytics for highway earthwork delay management.

AI Applications

- Predictive scheduling
- Delay forecasting
- Resource optimization
- Risk prioritization

Benefits

- Faster data processing
- Improved prediction accuracy
- Real-time decision support

7. Proposed Integrated Decision-Making Framework

The proposed framework integrates traditional project management tools with digital technologies.

Framework Components

Component	Purpose
CPM/PERT	Schedule management
AHP/Fuzzy-AHP	Risk prioritization
BIM	Real-time visualization
AI/ML Models	Predictive analytics
GIS Systems	Route and land analysis
Decision Support Systems	Managerial decision-making

Workflow

1. Identify delay factors.
2. Collect project data.
3. Rank risks using AHP/Fuzzy-AHP.
4. Predict delays using AI models.
5. Monitor project progress through BIM dashboards.
6. Implement corrective actions.

8. Case Study: Indian Highway Projects

Indian highway projects under the Hybrid Annuity Model (HAM) have shown significant delay challenges.

Key Findings

- Over 200 HAM projects experienced delays.
- Land acquisition accounted for the highest impact.
- Government approvals and poor planning contributed substantially.
- Projects using structured scheduling tools reported improved performance.

Suggested Mitigation Measures

- Early land acquisition planning
- Digital monitoring systems
- Stakeholder coordination platforms
- AI-assisted project scheduling

9. Discussion

Traditional delay management approaches mainly focus on reactive solutions after delays occur. However, modern highway projects require proactive and predictive decision-making systems.

The integration of:

- Multi-criteria decision-making,

- Artificial intelligence,
- BIM technologies,
- Predictive analytics,

can significantly improve project scheduling and risk management.

Data-driven systems also reduce human bias in decision-making and improve transparency.

10. Conclusion

Delays in highway construction projects remain a major challenge affecting economic growth and infrastructure development. Research findings show that land acquisition delays, regulatory approvals, poor planning, and financial instability are the primary causes of project overruns. Decision-making models such as CPM, PERT, AHP, Fuzzy-AHP, BIM, and AI-based systems provide effective tools for mitigating these delays.

The study concludes that integrated decision-support systems combining traditional scheduling techniques with digital technologies offer the most effective solution for modern highway project management. Future highway projects should adopt AI-enabled predictive systems and BIM-integrated management frameworks to improve efficiency, reduce delays, and optimize infrastructure delivery.

References

1. Hemanta Doloi, Anil Sawhney, and K.C. Iyer, "Structural Equation Model for Investigating Factors Affecting Delay in Indian Construction Projects," *Construction Management and Economics*, 2012.
2. Kamal Sharma and Manoj Kumar Trivedi, "Statistical Analysis of Delay-Causing Factors in Indian Highway Construction Projects under Hybrid Annuity Model," *Transportation Research Record*, 2023.
3. Saurabh Jindal and Indrasen Singh, "Application of Integrated Fuzzy-AHP and Decision Tree Model for Delay Management in Road Construction Projects," *Journal of Real Estate, Construction & Management*, 2023.
4. L. Pinky Devi and Sindhu, "Delay Analysis of Infrastructure Construction Projects in India," *Journal of The Institution of Engineers (India): Series A*, 2025.
5. Aziz, R.F. and Abdel-Hakam, A.A., "Exploring Delay Causes of Road Construction Projects in Egypt," *Alexandria Engineering Journal*, 2016.
6. Anastasopoulos, P.C. et al., "Empirical Assessment of the Likelihood and Duration of Highway Project Time Delays," *Journal of Construction Engineering and Management*, 2012.
7. Mahamid, I., "Risk Matrix for Factors Affecting Time Delay in Road Construction Projects," *Engineering, Construction and Architectural Management*, 2011.
8. Molenaar, K.R., "Programmatic Cost Risk Analysis for Highway Megaprojects," *Journal of Construction Engineering and Management*, 2005.
9. Durdyev, S. and Hosseini, M.R., "Causes of Delays on Construction Projects: A Comprehensive List," *International Journal of Managing Projects in Business*, 2020.
10. Ayushi Agnihotri and Rajesh Joshi, "Analysis of Delay Factors in Highway Construction Projects and Their Mitigation Strategies," *International Journal of Innovation in Engineering Research & Management*, 2024.